

**SUMMARY OF QUANTITIES**

**80% FED.  
20% STATE**

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURE
			CONSTRUCTION CODE	0004	0011
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	0.5	0.5	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	360	360	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4548	4548	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2632	2632	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	294	294	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	281	281	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1516	1516	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	505	505	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	84		84
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	55	55	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1
X5080600	MECHANICAL SPLICERS	EACH	120		120
X6650202	WOVEN WIRE FENCE REMOVAL	FOOT	588	588	
Z0001002	GUARDRAIL AGGREGATE EROSION CONTROL	TON	180	180	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	11		11
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0026407	TEMPORARY SHEET PILING	SQ FT	1912		1912
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0034105	MATERIAL TRANSFER DEVICE	TON	110	110	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	124		124

\* SPECIALTY ITEM

LAST SAVED = 12/16/2018  
PEN TABLE = W:\naif.tbl  
PLOT DRIVER = HP\pscript\back-hal.cpl

FILE NAME =	USER NAME = berzschmann	DESIGNED -	REVISED -
H:\080444\1194\cad\plans\0468693-Sht	000.dgn	DRAWN -	REVISED -
	PLOT SCALE = 40.0018' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/16/2018 10:20:28 AM	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**



**SUMMARY OF QUANTITIES**

SCALE: 1" = 20' SHEET NO. 3 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
534	109BR-1	HENDERSON	56	5
IL 94/116 OVER ELLISON CREEK		CONTRACT NO. 68693		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				