

SUMMARY OF QUANTITIES

**100% STATE BRIDGE-0014
PEORIA COUNTY**

CODE NO.	ITEM	UNIT	URBAN	TOTAL
42001300	PROTECTIVE COAT	SQYD	52	52
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQFT	290	290
50102400	CONCRETE REMOVAL	CUYD	26.2	26.2
50300255	CONCRETE SUPERSTRUCTURE	CUYD	26.2	26.2
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2710	2710
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2160	2160
50800515	BAR SPLICERS	EACH	40	40
52000110	PREFORMED JOINT STRIP SEAL	FOOT	136	136
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	19	19
52100520	ANCHOR BOLTS, 1"	EACH	38	38
60624600	CORRUGATED MEDIAN	SQFT	290	290
63300575	REMOVE ^{AND} RE ERECT RAIL ELEMENT OF EXISTING GUARDRAIL	FOOT	12.5	12.5
67100100	MOBILIZATION	LSUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CALMO	2	2
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	5500	5500
* 70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	400	400
* 70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	50	50
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQFT	1900	1900
70400100	TEMPORARY CONCRETE BARRIER	FOOT	350	350
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	112.5	112.5
* 78005110	PAVEMENT EPOXY MARKING - LINE 4"	FOOT	1000	1000
* 78005130	PAVEMENT EPOXY MARKING - LINE 6"	FOOT	320	320

**100% STATE BRIDGE-0014
PEORIA COUNTY**

CODE NO.	ITEM	UNIT	URBAN	TOTAL
* 78005150	PAVEMENT EPOXY MARKING - LINE 12"	FOOT	50	50
78300100	PAVEMENT MARKING REMOVAL	SQFT	500	500
X4403300	CONCRETE MEDIAN REMOVAL	SQFT	290	290
X5091755	PARAPET RAILING, SPECIAL	FOOT	40	40
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1	1
* X7200201	WIDTH RESTRICTION SIGNING	LSUM	1	1
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	19	19
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQFT	110.25	110.25
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQFT	19.5	19.5
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	3	3
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	3	3

* SPECIALTY ITEM

S:\GEN\DRAW\STD&PLNS\SQUAD BRIDGES\BRIDGE CONTRACTS\JOINTS\68995 SN072-0134\SN072-0134 US24avr\Kikapoocrk.dgn

FILE NAME = Revisions to D.Byers.dgn	USER NAME = jonesce	DESIGNED - C JONES	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES STRUCTURE NO. 072-0134	F.A.P. RTE. 317	SECTION (48B)-1	COUNTY PEORIA	TOTAL SHEETS 26	SHEET NO. 3
PLOT SCALE = 1/8" = 1' / IN.	CHECKED -	DRAWN - C JONES	REVISED -	SCALE: _____	SHEET NO. ____ OF ____ SHEETS	N.Abut. Rehab, Brge./Jt. Repl. CONTRACT NO. 68995 ILLINOIS FED. AID PROJECT				
PLOT DATE = 1/14/2011	DATE = 12/23/2010	REVISED -	REVISED -	STA. _____ TO STA. _____						