

SCHEDULE OF QUANTITIES

PROTECTIVE COAT

LOCATION	SQYD
N. & S. Parapet Walls Repl. Concrete Surface of Concrete Joint Blocks	7.2 44.8
TOTAL	52

MEDIAN REM. PARTIAL DEPTH

LOCATION	SQFT
Sta.187+72 Rt.60.5' to 191+67 Rt.62'	290
TOTAL	290

CONCRETE REMOVAL

LOCATION	CUYD
East Joint	25.2
TOTAL	25.2

CONCRETE SUPERSTRUCTURE

LOCATION	CUYD
East Joint	25.2
TOTAL	25.2

FURNISHING & ERECTING STRUCTURAL STEEL

LOCATION	Pound
East Joint	2710
TOTAL	2710

REINFORCEMENT BARS, EPOXY COATED

LOCATION	Pound
East Joint Replacement	2160
TOTAL	2160

BAR SPLICERS

LOCATION	EACH
East Joint Replacement	40
TOTAL	40

PREFORMED JOINT STRIP SEAL

LOCATION	FOOT
East Joint, Sidewalk, & Parapets	136
TOTAL	136

ELASTOMERIC BEARING ASSEMBLY, TYPE 2

LOCATION	EACH
East Abutment	19
TOTAL	19

ANCHOR BOLTS, 1"

LOCATION	EACH
East Abutment Bearing Mounts	38
TOTAL	38

CORRUGATED MEDIAN

LOCATION	SQFT
Sta.187+72 Rt.60.5' to 191+67 Rt.62'	290
TOTAL	290

REM & RE-ERECT RAIL ELEMENT OF EXISTING GUARDRAIL

LOCATION	FOOT
Face of North Parapet	12.5
TOTAL	12.5

MOBILIZATION

LOCATION	LSUM
Jobsite: SN.072-0134	1
TOTAL	1

CHANGEABLE MESSAGE SIGN

LOCATION	CALMO
Jobsite: SN.072-0134	2
TOTAL	2

PAVMT. MRKG. TAPE, TYPE 3, 4"

LOCATION	FOOT
Jobsite - SN.072-0134	5500
TOTAL	5500

PVMT. MRKG. TAPE, TYPE 3, 6"

LOCATION	FOOT
Jobsite - SN.072-0134	400
TOTAL	400

PVMT. MRKG. TAPE, TYPE 3, 12"

LOCATION	FOOT
Median Intro @ Exit I-474 Ramp	50
TOTAL	50

WORKZONE PVMT. MRKG. REM.

LOCATION	SQFT
Jobsite - SN.072-0134	1900
TOTAL	1900

TEMP. CONC. BARRIER

LOCATION	FOOT
EB. Traffic Control	225
WB. Traffic Control	125
TOTAL	350

RELOCATE TEMP. CONC. BARRIER

LOCATION	FOOT
EB. Traffic Control	112.5
TOTAL	112.5

S:\CEN\DRFT\STDPLNS\SQUAD BRIDGES\BRIDGE CONTRACTS\JOINTS\68995 SN072-0134\SN072-0134 US24vrKicKpooCrk.dgn

FILE NAME = SN072-0134 US24vrKicKpooCrk.dgn	USER NAME = jonesc	DESIGNED - C JONES	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES STRUCTURE NO. 072-0134	F.A.P. RTE. 317	SECTION (4BB1-1)	COUNTY PEORIA	TOTAL SHEETS 26	SHEET NO. 6
PLOT SCALE = 1/8" = 1' / IN.		DRAWN - C JONES		SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____		N.Abut. Rehab. Brgs./Jt. Repl.		CONTRACT NO. 68995 ILLINOIS FED. AID PROJECT		
PLOT DATE = 1/14/2011		CHECKED -								
		DATE - 12/28/2010								
		REVISED -								
		REVISED -								
		REVISED -								