

SUMMARY OF QUANTITIES

SHEET 2 OF 2

LOCATION OF WORK:	L20 FAP 804	L25 FAP 804	GRAHAM ST. & CHURCH ST.	CH 18 / (MONTICELLO RD.)
COUNTY:	MULTI-LANE URBAN CHAMPAIGN STA. 135+00.00 TO STA. 297+00.00	MULTI-LANE RURAL CHAMPAIGN STA. 297+00.00 TO STA. 415+00.00	2 LANE URBAN CHAMPAIGN	2 LANE URBAN CHAMPAIGN
FUNDING BREAKOUT:	80% FED 20% STATE	80% FED 20% STATE	100% VILLAGE OF SAVOY	100% CHAMPAIGN COUNTY
CONSTRUCTION TYPE CODE:	0005	0005	0005	0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	1.0			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	18124.0	10180.0	7792.0	48.0	104.0
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	3011.0	2138.0	811.0	16.0	46.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	122151.0	67932.0	51719.0	180.0	2320.0
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	590.0	168.0	60.0	182.0	180.0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1700.0	914.0	732.0		54.0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	538.0	476.0		30.0	32.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3364.0	1884.0	1455.0	8.0	17.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3011.0	2138.0	811.0	16.0	46.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	122151.0	67932.0	51719.0	180.0	2320.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	590.0	168.0	60.0	182.0	180.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1700.0	914.0	732.0		54.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	538.0	476.0		30.0	32.0
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	13240.0	7740.0	5500.0		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1689.0	1092.0	552.0	9.0	36.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1689.0	1092.0	552.0	9.0	36.0
* 88600100	DETECTOR LOOP, TYPE I	FOOT	2649.0	2409.0		240.0	
X4421000	PARTIAL DEPTH PATCHING	TON	66.0	57.0	9.0		
X7015005	CHANGEABLE MESSAGE SIGN	CA L DA	14.0	7.0	7.0		
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	96.0	96.0			
XZ193400	SURVEY MARKER, TYPE 2 (SPECIAL)	EACH	23.0	14.0	9.0		
Z0034105	MATERIAL TRANSFER DEVICE	TON	18813.0	10236.0	8577.0		

* SPECIALTY ITEMS

FILE NAME =	USER NAME = bucklesjj	DESIGNED - GAE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwidot\bucklesjj\d0210355\05708-shi-500.dgn		DRAWN - BBP	REVISED -		SCALE: NONE	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	804	(23,24,25)RS-5	CHAMPAIGN	61	6
PLOT SCALE = 40.0000' / 1" IN.		CHECKED -	REVISED -							CONTRACT NO. 70708			
PLOT DATE = 12/16/2010		DATE - 12/09/10	REVISED -		ILLINOIS FED. AID PROJECT								