TOTAL STRUCTURE SCHEDULE OF QUANTITIES
ACTUAL MEASUREMENTS

			SIMS INFORMATION		TOTAL STRUCTURE SCHEDULE OF QUANTITIES ACTUAL MEASUREMENTS																		
					DECK			APPROACH SLABS						PARAPETS (HUB, FACE & TOP)				TYPE B CURB (FACE & TOP)					
														HEIGHT	LENGTH			HEIGHT	LENGTH				
SN	ROUTE CARRIED	FEATURE CROSSED	LENGTH	WIDTH	LENGTH (E -E)	WIDTH (F-F)	TOTAL AREA (SY)	TOTAL LENGTH (FT)	LENGTH INSIDE PARAPET (FT)	WIDTH INSIDE PARAPET (FT)	LENGTH BEYOND PARAPET (FT)	WIDTH BEYOND PARAPET (O-O)	TOTAL AREA (SY)	3.6 FT TYPICAL	ALONG DECK (FT)	ALONG APPR. (FT)	TOTAL AREA (SY)	9 INCH TYPICAL	ALONG APPR. PVT.	TOTAL AREA (SY)	GRAND TOTAL (SQ YD)	RURAL	URBAN
010-0016	I-74(EB)	SANGAMON RIVER	350.2	46.8	392.2	46.2	2013.3	30.0	0	46.2	30.0	47.2	314.7	3.60	392.2	0.0	313.8	0.75	30.0	10.0	2652.0	X	
010-0017	I-74(WB)	SANGAMON RIVER	350.2	43.2	392.2	40.0	1743.1	30.0	0	40.0	30.0	41.0	273.3	3.60	392.2	0.0	313.8	0.75	30.0	10.0	2341.0	X	
010-0018	I-74(EB)	I-57	261.2	53.2	258.9	52.3	1504.3	50.0	13.5	52.3	36.5	40.3	483.8	3.60	258.9	13.5	228.7	0.00	36.5	0.0	2217.0		X
010-0019	I-74(WB)	I-57	261.2	53.2	258.9	52.3	1504.3	50.0	13.5	52.3	36.5	40.3	483.8	3.60	258.9	13.5	228.7	0.00	36.5	0.0	2217.0		X
010-0020	I-74	MARKET ST(FAU 7169)	146.5	121.2	144.2	115.5	1850.2	50.0	18	115.5	32.0	78.5	1020.2	3.60	144.2	18.0	288.3	0.75	32.0	10.7	3170.0		X
010-0021	I-74	IC RR & TR 158	725.0	121.2	722.7	115.2	9247.8	50.0	24	115.2	26.0	116.2	1285.6	3.60	722.7	24.0	1233.1	0.75	26.0	8.7	11776.0		X
010-0022	I-74(WB)	W FORK SALINE BRANCH	100.2	60.5	97.9	57.3	623.1	20.0	12	57.3	8.0	58.3	256.4	3.60	97.9	12.0	97.5	0.75	8.0	2.7	980.0		X
010-0023	I-74(EB)	W FORK SALINE BRANCH	100.2	60.5	97.9	57.3	623.1	20.0	12	57.3	8.0	58.3	256.4	3.60	97.9	12.0	97.5	0.75	8.0	2.7	980.0		X
010-0024	I-74	US 45(FAP 800)	186.8	97.2	184.5	91.7	1878.9	52.0	12	91.7	40.0	48.0	671.1	3.60	184.5	12.0	333.6	0.75	40.0	13.3	2897.0		X
010-0025	I-74(EB)	SALINE BRANCH	164.7	43.2	162.4	40.0	721.6	23.2	12	40.0	6.0	32.0	149.3	3.60	162.4	12.0	149.1	0.00	6.0	0.0	1021.0		X
010-0026	I-74(WB)	SALINE BRANCH	164.7	43.2	162.4	40.0	721.6	23.2	12	40.0	6.0	32.0	149.3	3.60	162.4	12.0	149.1	0.00	6.0	0.0	1021.0		X
010-0027	I-74(WB)	SALINE DRAIN DITCH	165.5	42.2	163.2	39.0	707.1	26.6	13.5	39.0	13.1	42.2	239.8	3.60	163.2	13.5	152.1	0.75	13.1	4.4	1104.0	X	
010-0028	I-74(EB)	SALINE DRAIN DITCH	165.5	42.2	163.2	39.0	707.1	26.6	13.5	39.0	13.1	42.2	239.8	3.60	163.2	13.5	152.1	0.75	13.1	4.4	1104.0	X	
010-0029	I-74(WB)	SALT FORK RIVER	164.5	42.2	162.2	39.0	702.7	20.0	10	39.0	10.0	42.2	180.4	3.60	162.2	10.0	145.7	0.75	10.0	3.3	1033.0	X	
010-0030	I-74(EB)	SALT FORK RIVER	164.5	42.2	162.2	39.0	702.7	20.0	10	39.0	10.0	42.2	180.4	3.60	162.2	10.0	145.7	0.75	10.0	3.3	1033.0	X	
010-0031	I-74(WB)	OVER UPRR	171.3	42.2	169.0	39.0	732.2	24.4	12	39.0	12.4	42.2	220.3	3.60	169.0	12.0	154.4	0.75	12.4	4.1	1111.0	X	
010-0032	I-74(EB)	OVER UPRR	171.3	42.2	169.0	39.0	732.2	24.4	12	39.0	12.4	42.2	220.3	3.60	169.0	12.0	154.4	0.75	12.4	4.1	1111.0	X	
057-0006	I-55/I-74	OVER UPRR	237.0	70.8	234.7	67.6	1761.3	30.0	30	67.6	0.0	70.8	450.3	3.60	234.7	21.0	221.3	0.75	18.0	3.0	2436.0		X
057-0007	I-55/I-74 NB	ICG RR	226.0	69.0	223.7	65.8	1635.3	30.0	30	65.8	0.0	69.0	438.7	3.60	223.7	21.0	212.5	0.75	18.0	3.0	2290.0		X
057-0008	I-55/I-74 NB	SIX PTS RD/FAU 6369	130.0	65.6	127.7	62.4	885.2	30.0	30	62.4	0.0	65.6	416.0	3.60	127.7	21.0	135.7	0.75	18.0	3.0	1440.0		X
057-0009	I-55/I-74 SB	SIX PTS.RD/FAU 6369	130.0	65.6	127.7	62.4	885.2	30.0	30	62.4	0.0	65.6	416.0	3.60	127.7	21.0	135.7	0.75	18.0	3.0	1440.0		X
057-0010	I-55/I-74 SB	SUGAR CREEK	283.8	65.6	281.5	62.4	1951.5	30.0	30	62.4	0.0	65.6	416.0	3.60	281.5	21.0	258.8	0.75	18.0	3.0	2630.0		X
057-0011	I-55/I-74 NB	SUGAR CREEK	283.8	65.6	281.5	62.4	1951.5	30.0	30	62.4	0.0	65.6	416.0	3.60	281.5	21.0	258.8	0.75	18.0	3.0	2630.0		X
057-0016	I-55/I-74 NB	WASH.ST/FAU 6360	183.3	72.3	181.0	69.1	1389.4	30.0	30	69.1	0.0	72.3	460.7	3.60	181.0	21.0	178.4	0.75	18.0	3.0	2032.0		X
057-0017	I-55/I-74 SB	WASH.ST/FAU 6360	183.3	72.3	181.0	69.1	1389.4	30.0	30	69.1	0.0	72.3	460.7	3.60	181.0	21.0	178.4	0.75	18.0	3.0	2032.0		X
057-0018	I-55/I-74 NB	OLD 150 & N&W RR	448.0	65.1	445.7	61.9	3065.2	30.0	30	61.9	0.0	65.1	412.7	3.60	445.7	21.0	390.1	0.75	18.0	3.0	3872.0		X
057-0019	I-55/I-74 SB	OLD 150 & N&W RR	448.0	65.1	445.7	61.9	3065.2	30.0	30	61.9	0.0	65.1	412.7	3.60	445.7	21.0	390.1	0.75	18.0	3.0	3872.0		X
057-0043	I-74	ROCK CREEK	85.0	44.3	82.7	39.0	358.2	0.0	0	39.0	0.0	44.3	0.0	3.45	82.7	0.0	63.4	0.00	0.0	0.0	422.0	X	
057-0044	I-74	ROCK CREEK	85.0	44.3	82.7	39.0	358.2	0.0	0	39.0	0.0	44.3	0.0	3.45	82.7	0.0	63.4	0.00	0.0	0.0	422.0	X	
057-0045	I-74/WB	N. & W. RR .	233.0	42.6	230.7	39.4	1009.8	30.0	12	39.4	18.0	42.6	275.5	3.60	230.7	12.0	203.7	0.75	6.0	2.0	1492.0	X	
057-0046	I-74/EB	N. & W. RR	233.0	42.6	230.7	39.4	1009.8	30.0	12	39.4	18.0	42.6	275.5	3.60	230.7	12.0	203.7	0.75	6.0	2.0	1492.0	X	
057-0047	I-74 EB	US 51/S.OF BLOOMNGTN	181.0	53.7	178.7	50.5	1002.5	0.0	0	50.5	0.0	53.7	0.0	3.60	178.7	15.0	166.9	0.00	0.0	0.0	1170.0		X
057-0048	I-74 WB	US 51/S.OF BLOOMNGTN	181.0	53.7	178.7	50.5	1002.5	0.0	0	50.5	0.0	53.7	0.0	3.60	178.7	15.0	166.9	0.00	0.0	0.0	1170.0		X
057-0120	I-74 EB	LITTLE KICKAPOO CR	163.9	43.2	161.6	40.0	718.2	30.0	0	40.0	30.0	40.8	272.0	3.60	161.6	0.0	129.3	0.75	30.0	10.0	1130.0		X
057-0121	I-74 WB	LITTLE KICKAPOO CR	163.9	43.2	161.6	40.0	718.2	30.0	0	40.0	30.0	40.8	272.0	3.60	161.6	0.0	129.3	0.75	30.0	10.0	1130.0		X
057-0125	I-74 EB	KICKAPOO CR	191.5	43.2	189.2	40.0	840.8	30.0	12	40.0	18.0	41.0	270.7	3.60	189.2	12.0	170.5	0.75	18.0	6.0	1288.0		X
057-0126	I-74 WB	LITTLE KICKAPOO CR	191.5	43.2	189.2	40.0	840.8	30.0	12	40.0	18.0	41.0	270.7	3.60	189.2	12.0	170.5	0.75	18.0	6.0	1288.0		X
057-0128	I-74 EB	LITTLE KICKAPOO CR	109.5	42.0	109.5	38.8	472.1	0.0	0	38.8	0.0	42.0	0.0	3.60	109.5	15.0	111.6	0.00	0.0	0.0	584.0		X
057-0129	I-74 WB	LITTLE KICKAPOO CR	109.5	43.2	109.5	40.0	486.7	30.0	0	40.0	30.0	41.0	273.3	3.60	109.5	0.0	87.6	0.75	30.0	10.0	858.0		X

*FY2011 BRIDGE DECK SEALING
**CHAMPAIGN, MCLEAN & VERMILION

FILE NAME = c:\pw_work\pwidot\cearlockjd\d0185207\D70861-sht-schedule.dgn	USER NAME = cearlockjd	DESIGNED - TJB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TOTAL STRUCTURE SCHEDULE OF QUANTITES ACTUAL MEASUREMENTS	F.A.I. RTE. 74	SECTION *	COUNTY **	TOTAL SHEETS 19 / SHEET NO. 10
	PLOT SCALE = 40.0000 ' / IN.	DRAWN - BBP	REVISED -					CONTRACT NO. 70861	
	PLOT DATE = 11/15/2010	CHECKED -	REVISED -		SCALE: NONE / SHEET NO. 1 OF 2 SHEETS / STA. TO STA.		ILLINOIS FED. AID PROJECT		
		DATE - 09/20/10	REVISED -						