

# MCLEAN COUNTY STRUCTURES

## ACTUAL MEASUREMENTS

MCLEAN COUNTY STRUCTURES SCHEDULE OF QUANTITIES																							
ACTUAL MEASUREMENTS																							
SN	ROUTE CARRIED	FEATURE CROSSED	SIMS INFORMATION		DECK			APPROACH SLABS					PARAPETS (HUB, FACE & TOP)			TYPE B CURB (FACE & TOP)			GRAND TOTAL (SQ YD)	RURAL	URBAN		
					LENGTH (E-E)	WIDTH (F-F)	TOTAL AREA (SY)	TOTAL LENGTH (FT)	LENGTH INSIDE PARAPET (FT)	WIDTH INSIDE PARAPET (FT)	LENGTH BEYOND PARAPET (FT)	WIDTH BEYOND PARAPET (O-O)	TOTAL AREA (SY)	HEIGHT	LENGTH		TOTAL AREA (SY)	HEIGHT				LENGTH	TOTAL AREA (SY)
			LENGTH	WIDTH		3.6 FT TYPICAL	ALONG DECK (FT)	ALONG APPR. (FT)	9 INCH TYPICAL	ALONG APPR. PVT.													
057-0006	I-55/I-74	OVER UPRR	237.0	70.8	234.7	67.6	1761.3	30.0	30	67.6	0.0	70.8	450.3	3.60	234.7	21.0	221.3	0.75	18.0	3.0	2436.0		X
057-0007	I-55/I-74 NB	ICG RR	226.0	69.0	223.7	65.8	1635.3	30.0	30	65.8	0.0	69.0	438.7	3.60	223.7	21.0	212.5	0.75	18.0	3.0	2290.0		X
057-0008	I-55/I-74 NB	SIX PTS RD/FAU 6369	130.0	65.6	127.7	62.4	885.2	30.0	30	62.4	0.0	65.6	416.0	3.60	127.7	21.0	135.7	0.75	18.0	3.0	1440.0		X
057-0009	I-55/I-74 SB	SIX PTS.RD/FAU 6369	130.0	65.6	127.7	62.4	885.2	30.0	30	62.4	0.0	65.6	416.0	3.60	127.7	21.0	135.7	0.75	18.0	3.0	1440.0		X
057-0010	I-55/I-74 SB	SUGAR CREEK	283.8	65.6	281.5	62.4	1951.5	30.0	30	62.4	0.0	65.6	416.0	3.60	281.5	21.0	258.8	0.75	18.0	3.0	2630.0		X
057-0011	I-55/I-74 NB	SUGAR CREEK	283.8	65.6	281.5	62.4	1951.5	30.0	30	62.4	0.0	65.6	416.0	3.60	281.5	21.0	258.8	0.75	18.0	3.0	2630.0		X
057-0016	I-55/I-74 NB	WASH.ST/FAU 6360	183.3	72.3	181.0	69.1	1389.4	30.0	30	69.1	0.0	72.3	460.7	3.60	181.0	21.0	178.4	0.75	18.0	3.0	2032.0		X
057-0017	I-55/I-74 SB	WASH.ST/FAU 6360	183.3	72.3	181.0	69.1	1389.4	30.0	30	69.1	0.0	72.3	460.7	3.60	181.0	21.0	178.4	0.75	18.0	3.0	2032.0		X
057-0018	I-55/I-74 NB	OLD 150 & N&W RR	448.0	65.1	445.7	61.9	3065.2	30.0	30	61.9	0.0	65.1	412.7	3.60	445.7	21.0	390.1	0.75	18.0	3.0	3872.0		X
057-0019	I-55/I-74 SB	OLD 150 & N&W RR	448.0	65.1	445.7	61.9	3065.2	30.0	30	61.9	0.0	65.1	412.7	3.60	445.7	21.0	390.1	0.75	18.0	3.0	3872.0		X
057-0043	I-74	ROCK CREEK	85.0	44.3	82.7	39.0	358.2	0.0	0	39.0	0.0	44.3	0.0	3.45	82.7	0.0	63.4	0.00	0.0	0.0	422.0	X	
057-0044	I-74	ROCK CREEK	85.0	44.3	82.7	39.0	358.2	0.0	0	39.0	0.0	44.3	0.0	3.45	82.7	0.0	63.4	0.00	0.0	0.0	422.0	X	
057-0045	I-74/WB	N. & W. RR	233.0	42.6	230.7	39.4	1009.8	30.0	12	39.4	18.0	42.6	275.5	3.60	230.7	12.0	203.7	0.75	6.0	2.0	1492.0	X	
057-0046	I-74/EB	N. & W. RR	233.0	42.6	230.7	39.4	1009.8	30.0	12	39.4	18.0	42.6	275.5	3.60	230.7	12.0	203.7	0.75	6.0	2.0	1492.0	X	
057-0047	I-74 EB	US 51/S.OF BLOOMNGTN	181.0	53.7	178.7	50.5	1002.5	0.0	0	50.5	0.0	53.7	0.0	3.60	178.7	15.0	166.9	0.00	0.0	0.0	1170.0		X
057-0048	I-74 WB	US 51/S.OF BLOOMNGTN	181.0	53.7	178.7	50.5	1002.5	0.0	0	50.5	0.0	53.7	0.0	3.60	178.7	15.0	166.9	0.00	0.0	0.0	1170.0		X
057-0120	I-74 EB	LITTLE KICKAPOO CR	163.9	43.2	161.6	40.0	718.2	30.0	0	40.0	30.0	40.8	272.0	3.60	161.6	0.0	129.3	0.75	30.0	10.0	1130.0		X
057-0121	I-74 WB	LITTLE KICKAPOO CR	163.9	43.2	161.6	40.0	718.2	30.0	0	40.0	30.0	40.8	272.0	3.60	161.6	0.0	129.3	0.75	30.0	10.0	1130.0		X
057-0125	I-74 EB	KICKAPOO CR	191.5	43.2	189.2	40.0	840.8	30.0	12	40.0	18.0	41.0	270.7	3.60	189.2	12.0	170.5	0.75	18.0	6.0	1288.0		X
057-0126	I-74 WB	LITTLE KICKAPOO CR	191.5	43.2	189.2	40.0	840.8	30.0	12	40.0	18.0	41.0	270.7	3.60	189.2	12.0	170.5	0.75	18.0	6.0	1288.0		X
057-0128	I-74 EB	LITTLE KICKAPOO CR	109.5	42.0	109.5	38.8	472.1	0.0	0	38.8	0.0	42.0	0.0	3.60	109.5	15.0	111.6	0.00	0.0	0.0	584.0		X
057-0129	I-74 WB	LITTLE KICKAPOO CR	109.5	43.2	109.5	40.0	486.7	30.0	0	40.0	30.0	41.0	273.3	3.60	109.5	0.0	87.6	0.75	30.0	10.0	858.0		X
057-0133	I-74 EB	N FORK SALT CREEK	139.0	43.2	136.7	40.0	607.4	30.0	0	40.0	30.0	43.2	288.0	3.60	136.7	0.0	109.3	0.75	30.0	10.0	1015.0	X	
057-0134	I-74 WB	N FORK SALT CREEK	139.0	43.2	136.7	40.0	607.4	30.0	0	40.0	30.0	43.2	288.0	3.60	136.7	0.0	109.3	0.75	30.0	10.0	1015.0	X	
057-0233	I-55/I-74 NB	COUNTY RD SUDDITH RD	156.0	65.1	153.7	61.9	1056.9	30.0	15	61.9	15.0	65.1	423.3	3.60	153.7	15.0	146.9	0.75	15.0	5.0	1633.0		X
057-0234	I-55/I-74 SB	COUNTY RD SUDDITH RD	156.0	65.1	153.7	61.9	1056.9	30.0	15	61.9	15.0	65.1	423.3	3.60	153.7	15.0	146.9	0.75	15.0	5.0	1633.0		X
<b>GRAND TOTALS (SQ YD):</b>																		<b>42,416</b>	<b>5,858</b>	<b>36,558</b>			

FILE NAME =	USER NAME = ceorlockjd	DESIGNED - TJB	REVISED -
ct:\pw\work\p\dot\ceorlockjd\0185207\0570861-sht-schedule.dgn		DRAWN - BBP	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 11/15/2010	DATE - 09/20/10	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**MCLEAN COUNTY STRUCTURES  
ACTUAL MEASUREMENTS**

SCALE: NONE      SHEET NO. 1 OF 1 SHEETS      STA.      TO STA.

*FY2011 BRIDGE DECK SEALING		**CHAMPAIGN, MCLEAN & VERMILION	
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS
74	*	**	19
			SHEET NO. 16
CONTRACT NO. 70861			
ILLINOIS FED. AID PROJECT			