

ILLINOIS DEPARTMENT OF TRANSPORTATION

CODE NO.	ITEM	UNIT	TOTAL	
			80% FEDERAL 20% STATE	FAP315 US 136 0005 80% FEDERAL 20% STATE
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	716.0	716.0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	202.0	202.0
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	90.0	90.0
40600300	AGGREGATE (PRIME COAT)	TON	264.0	264.0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4290.0	4290.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3343.0	3343.0
40600990	TEMPORARY RAMP	SQ YD	334.0	334.0
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	8563.0	8563.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	422.0	422.0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	2569.0	2569.0
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	131952.0	131952.0
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	500.0	500.0
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SQ YD	175.0	175.0
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SQ YD	30.0	30.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3626.0	3626.0
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	23860.0	23860.0
64200105	SHOULDER RUMBLE STRIPS	FOOT	73864.0	73864.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8.0	8.0
67100100	MOBILIZATION	L SUM	1.0	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10.0	10.0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	11080.8	11080.8
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	89587.0	89587.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1231.0	1231.0
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	89587.0	89587.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	462.0	462.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	462.0	462.0

*SPECIALTY ITEM

FILE NAME = c:\pwwork\pwwork\laughlinr1\d0217938\d0217938\2022-sht-500.dgn	USER NAME = laughlinr1	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 315	SECTION 116RS-4	COUNTY LOGAN	TOTAL SHEETS 27	SHEET NO. 3
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 72C22			
PLOT DATE = Jan-03-2011 08:27:27AM	DATE -	REVISED -	REVISED -		ILLINOIS FED. AID PROJECT							