

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		80% FEDERAL 20% STATE 0014	
20200500 35400300	EARTH EXCAVATION (WIDENING) PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	CU YD SQ YD	91 408	91 408	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11	11	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	12	12	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	106	106	
44004250	PAVED SHOULDER REMOVAL	SQ YD	272	272	
50102400	CONCRETE REMOVAL	CU YD	27.3	27.3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	27.3	27.3	
50300260	BRIDGE DECK GROOVING	SQ YD	2744	2744	
50300300	PROTECTIVE COAT	SQ YD	3055	3055	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2260	2260	
50800515	BAR SPLICERS	EACH	22	22	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	44	44	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100 70106700	SHORT TERM PAVEMENT MARKING TEMPORARY RUMBLE STRIPS	FOOT EACH	120 3	120 3	
70301000 70400100	WORK ZONE PAVEMENT MARKING REMOVAL TEMPORARY CONCRETE BARRIER	SQ FT FOOT	40 900	40 900	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	900	900	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2682	2682	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	613	613	
XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	3,029	3,029	
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	3029	3029	
Z0006202	BRIDGE DECK HYDRO-SCARIFICATION 3/4"	SQ YD	3,029	3,029	
Z0015802	PLUG EXISTING DECK DRAINS	EACH	212	212	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	2	2	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	142	142	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	84	84	
Z0018000	DRAINAGE SCUPPERS (SPECIAL)	EACH	20	20	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0034390	MODULAR EXPANSION JOINT 6"	FOOT	44	44	

*SPECIALTY ITEM

FILE NAME *	USER NAME = #USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL*		DRAWN -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	774	(102BR)BR-2	Shelby	19	3
	PLOT SCALE = #SCALE*	CHECKED -	REVISED -									
	PLOT DATE = #DATE*	DATE -	REVISED -									CONTRACT NO. 74483
[ILLINOIS] FED. AID PROJECT												