



▨ DRAINAGE SCUPPERS, (SPECIAL) QUANTITY = 20 EACH  
- DECK DRAINS TO BE PLUGGED QUANTITY = 212 EACH  
\* FOR INFORMATION ONLY  
COST INCLUDED WITH CONCRETE SUPERSTRUCTURE

PATCH NO.	SIZE	DECK SLAB REPAIR (PART DEPTH)		
		SO FT	SO FT	SO FT
60	2.0 x 3.0			6.0
61	2.0 x 4.0			8.0
*62	3.2 x 4.1			
*63	3.2 x 4.1			
64	14.0 x 2.0	28.0		
145	2.0 x 4.0			8.0
146	2.0 x 8.0			16.0
147	2.0 x 12.0			24.0
148	2.0 x 8.0			16.0
*149	3.2 x 4.1			
*150	3.2 x 4.1			
151	4.0 x 4.0			16.0
TOTAL		769	16	1282

PATCH NO.	SIZE	DECK SLAB REPAIR (PART DEPTH)		
		SO FT	SO FT	SO FT
PARTIAL DEPTH (FOR INFORMATION ONLY)				
	769 / 9 =	85.4		
	USE	85	SO YD	
FULL DEPTH, TYPE 1				
	16 / 9 =	1.8		
	USE	2	SO YD	
FULL DEPTH, TYPE 2				
	1282 / 9 =	142.4		
	USE	142	SO YD	

PATCH NO.	SIZE	DECK SLAB REPAIR (PART DEPTH)		
		SO FT	SO FT	SO FT

PATCH NO.	SIZE	DECK SLAB REPAIR (PART DEPTH)		
		SO FT	SO FT	SO FT

PATCH NO.	SIZE	DECK SLAB REPAIR (PART DEPTH)		
		SO FT	SO FT	SO FT

THE LOCATIONS AND SIZES SHOWN GRAPHICALLY ABOVE ARE APPROXIMATE. SEE THIS TABLE FOR ACTUAL SIZES.

PATCHING LEGEND

□ PARTIAL DEPTH (FOR INFORMATION ONLY)

▨ FULL DEPTH

DATE OF SURVEY: 9-22-10  
SURVEY BY: MEA, ESS, KLB  
RSW, DPM  
METHOD OF SURVEY: VISUAL

BRIDGE DECK PATCHING  
SHELBY COUNTY  
IL 128 OVER THE  
KASKASKIA RIVER  
1 MILE SE OF  
COWDEN  
SN 087-0023

023

FILE NAME =	USER NAME = teasleyk	DESIGNED -	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		BRIDGE DECK PATCHING SN. 087-0023		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pw\work\p\idot\teasleyk\08207751\0774	83-sh-t-brpatch.dgn	DRAWN -	REVISIONS -					774	102881BR-2	Shelby	19	14	
	PLOT SCALE = 50,0000 ' / IN.	CHECKED -	REVISIONS -										
	PLOT DATE = 12/16/2010	DATE -	REVISIONS -										
								SCALE: -----	SHEET NO. 9 OF 14 SHEETS	STA. -----	TO STA. -----	FED. ROAD DIST. NO. -----	ILLINOIS FED. AID PROJECT