



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

March 1, 2011

SUBJECT: FAP Route 712 (IL 48)  
Section D7 PAVT PATCHING 2011-1  
Macon County  
Contract No. 74486  
Item No. 94, March 11, 2011 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised sheet 2 of the Fold-Up Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read "Ted B. Walschleger", followed by the letters "P.E." in a smaller font.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Roger Driskell, Region 4, District 7; Mike Renner; Estimates

TBW:DB:jc

3/1/2011  
c:\pw\_work\pwid\hemmenje\0209349\0774486-1

FAP 712 (ILL 48)  
D7 PAVT PATCHING 2011-1  
MACON COUNTY  
SHEET 2 OF 5  
CONTRACT NO. 74486

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	INDEX OF SHEETS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	LOCATION MAP
5	PATCHING SCHEDULE

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 4:

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-02 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 420001-07 PAVEMENT JOINTS
- 421001-02 BAR REINFORCEMENT FOR CONTINUOUSLY REINFORCED PAVEMENT
- 442001-04 CLASS A PATCHES
- 442201-03 CLASS C AND D PATCHES
- 701101-02 OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
- 701106-02 OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
- 701601-07 URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
- 701901-01 TRAFFIC CONTROL DEVICES

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE WORK INCLUDED IN SECTION D7 PAVT PATCHING 2011-1 CONSISTS OF CLASS A AND CLASS D PATCHES. THE PROJECT IS LOCATED IN MACON COUNTY ON FAP 712 (IL 48) FROM PERSHING ROAD TO JUST NORTH OF BRUSH COLLEGE ROAD.

THE ACTUAL LOCATIONS OF PAVEMENT PATCHING AND FINAL QUANTITIES SHALL BE DETERMINED BY THE ENGINEER IN THE FIELD.

ALL LONGITUDINAL REINFORCEMENT BARS SHALL BE #6 BARS.

THE FOLLOWING MIXTURE DESIGN REQUIREMENTS ARE APPLICABLE TO THIS PROJECT:



- APPLICATION: HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90
- PG GRADE: PG 64-22
- DESIGN AIR VOIDS: 4.0% @ Ndesign = 90
- MIXTURE COMPOSITION: IL-19.0
- FRICTION AGGREGATE: N/A

**1** REVISED 3-1-11