

PAVING SCHEDULE			LENGTH	PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NTO
STATION	TO	STATION	FEET	FEET	SQ YD	GALLON	TON	SQ. YD.	TON
689+81.63	TO	729+51.30	3,969.7	24.0	10,585.8	1,058.6	21.2	10,585.8	1,037.4
729+51.30	TO	729+93.71	42.4	0.0	0.0	0.0	0.0	0.0	0.0
729+93.71	TO	742+61.63	1,267.9	24.0	3,381.1	338.1	6.8	3,381.1	331.3
742+61.63	TO	795+41.63	5,280.0	24.0	14,080.0	1,408.0	28.2	14,080.0	1,379.8
795+41.63	TO	836+07.57	4,065.9	24.0	10,842.5	1,084.3	21.7	10,842.5	1,062.6
836+07.57	TO	836+37.57	30.0	0.0	0.0	0.0	0.0	0.0	0.0
836+37.57	TO	838+27.25	189.7	24.0	505.8	50.6	1.0	505.8	49.6
838+27.25	=	838+62.16	0.0	24.0	0.0	0.0	0.0	0.0	0.0
838+62.16	TO	871+80.22	3,318.1	24.0	8,848.2	884.8	17.7	8,848.2	867.1
871+80.22	=	871+21.26	0.0	24.0	0.0	0.0	0.0	0.0	0.0
871+21.26	TO	924+01.26	5,280.0	24.0	14,080.0	1,408.0	28.2	14,080.0	1,379.8
924+01.26	TO	976+81.26	5,280.0	24.0	14,080.0	1,408.0	28.2	14,080.0	1,379.8
976+81.26	TO	1029+61.26	5,280.0	24.0	14,080.0	1,408.0	28.2	14,080.0	1,379.8
1029+61.26	TO	1082+41.26	5,280.0	24.0	14,080.0	1,408.0	28.2	14,080.0	1,379.8
1082+41.26	TO	1135+21.26	5,280.0	24.0	14,080.0	1,408.0	28.2	14,080.0	1,379.8
1135+21.26	TO	1188+01.26	5,280.0	24.0	14,080.0	1,408.0	28.2	14,080.0	1,379.8
1188+01.26	TO	1207+23.26	1,922.0	24.0	5,125.3	512.5	10.3	5,125.3	502.3
1207+23.26	=	1206+92.54	0.0	24.0	0.0	0.0	0.0	0.0	0.0
1206+92.54	TO	1229+20.94	2,228.4	24.0	5,942.4	594.2	11.9	5,942.4	582.4
1229+20.94	TO	1246+91.91	1,771.0	24.0	4,722.6	472.3	9.4	4,722.6	462.8
1246+91.91	TO	1285+59.00	3,867.1	24.0	10,312.2	1,031.2	20.6	10,312.2	1,010.6
SHEET TOTALS			59,632		158,826	15,883	318	158,826	15,565

PAVEMENT MARKING SCHEDULE												LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING-LINE 4" (YELLOW)	TEMPORARY PAVEMENT MARKING-LINE 4" (YELLOW SKIP-DASH)	TEMPORARY PAVEMENT MARKING-LINE 4" (WHITE)	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING-LINE 4" (YELLOW)	PAINT PAVEMENT MARKING-LINE 4" (YELLOW SKIP-DASH)	PAINT PAVEMENT MARKING-LINE 4" (WHITE)
STATION	TO	STATION	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT								
689+81.63	TO	729+51.30	3,969.7	1,190.9	0.0	992.4	7,939.3	3,109.3	0.0	992.4	7,939.3									
729+51.30	TO	729+93.71	42.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	10.6	84.8								
729+93.71	TO	742+61.63	1,267.9	380.4	0.0	317.0	2,535.8	993.1	0.0	317.0	2,535.8									
742+61.63	TO	795+41.63	5,280.0	1,584.0	0.0	1,320.0	10,560.0	4,135.6	0.0	1,320.0	10,560.0									
795+41.63	TO	836+07.57	4,065.9	1,219.8	0.0	1,016.5	8,131.9	3,184.7	0.0	1,016.5	8,131.9									
836+07.57	TO	836+37.57	30.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	7.5	60.0								
836+37.57	TO	838+27.25	189.7	56.9	0.0	47.4	379.4	148.6	0.0	47.4	379.4									
838+27.25	=	838+62.16	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0								
838+62.16	TO	871+80.22	3,318.1	995.4	0.0	829.5	6,636.1	2,598.9	0.0	829.5	6,636.1									
871+80.22	=	871+21.26	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0								
871+21.26	TO	924+01.26	5,280.0	1,584.0	0.0	1,320.0	10,560.0	4,135.6	0.0	1,320.0	10,560.0									
924+01.26	TO	976+81.26	5,280.0	1,584.0	0.0	1,320.0	10,560.0	4,135.6	0.0	1,320.0	10,560.0									
976+81.26	TO	1029+61.26	5,280.0	1,584.0	0.0	1,320.0	10,560.0	4,135.6	0.0	1,320.0	10,560.0									
1029+61.26	TO	1082+41.26	5,280.0	1,584.0	0.0	1,320.0	10,560.0	4,135.6	0.0	1,320.0	10,560.0									
1082+41.26	TO	1135+21.26	5,280.0	1,584.0	0.0	1,320.0	10,560.0	4,135.6	0.0	1,320.0	10,560.0									
1135+21.26	TO	1188+01.26	5,280.0	1,584.0	0.0	1,320.0	10,560.0	4,135.6	0.0	1,320.0	10,560.0									
1188+01.26	TO	1207+23.26	1,922.0	576.6	0.0	480.5	3,844.0	1,505.4	0.0	480.5	3,844.0									
1207+23.26	=	1206+92.54	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0								
1206+92.54	TO	1229+20.94	2,228.4	668.5	0.0	557.1	4,456.8	1,745.4	0.0	557.1	4,456.8									
1229+20.94	TO	1246+91.91	1,771.0	531.3	828.0	442.7	3,541.9	1,663.1	828.0	442.7	3,541.9									
1246+91.91	TO	1285+59.00	3,867.1	1,160.1	632.0	966.8	7,734.2	3,239.6	632.0	966.8	7,734.2									
SHEET TOTALS			59,632	17,868	1,460	14,890	119,119	47,137	1,460	14,908	119,264									

PATCHING SCHEDULE					
LOCATION	CLASS D PATCHES, TYPE II, 14"	CLASS D PATCHES, TYPE III, 14"	CLASS D PATCHES, TYPE IV, 14"	PARTIAL DEPTH PATCHING (SPECIAL)	HOT-MIX ASPHALT FOR PATCHING
	SQ YD	SQ YD	SQ YD	SQ YD	TON
FAP 95 (IL 33)	4,208	2,666	3,890	11,352	5,086

TEMPORARY RAMPS SCHEDULE				LENGTH	WIDTH	AREA
LOCATION				FEET	FEET	SQ YD
689+81.63	TO	689+86.63	BEGINNING OF PROJECT	5.0	24.0	13.3
729+46.30	TO	729+51.30	W. APPROACH SN	5.0	24.0	13.3
729+93.71	TO	729+98.71	E. APPROACH SH	5.0	24.0	13.3
836+02.57	TO	836+07.57	W. APPROACH SN	5.0	24.0	13.3
836+37.57	TO	836+42.57	E. APPROACH SH	5.0	24.0	13.3
1285+53.00	TO	1285+58.00	END OF PROJECT	5.0	24.0	13.3
TOTAL=						80

FILE NAME =	USER NAME = swartzrw	DESIGNED -	REVISED -
ca:\pwwork\pwwork\swartzrw\d0241838\d77	006-shltschdgn	DRAWN -	REVISED -
	PLOT SCALE = 50,0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/18/2018	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: NA SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	(5,6)RS-2A	JASPER	19	5
CONTRACT NO. 74506			ILLINOIS FED. AID PROJECT	