

RESURFACING SCHEDULE										
STA.	TO	STA.	WIDTH	LENGTH	HMA SURF CRSE	HMA BINDER	BITUMINOUS	AGGREGATE	HMA	AGGREGATE
					MIX D, N90	COURSE, IL 19.0, N90	MATERIAL (PRIME COAT)	(PRIME COAT)	SHOULDERS	WEDGE SHOULDER
					TON	TON	TON	TON	TON	TON
3214+42	TO	3261+00	24	4658	1043.4	1565	3.9	18.6		
3261+00	TO	3284+00	57	2300	1223.6	1836	4.6	21.9		
3284+00	TO	3341+38	24	5738	1285.3	1928	4.8	23.0		
3214+42	TO	3271+78	8	5736					2142	
3272+66	TO	3341+38	8	6872					2566	
3214+42	TO	3271+78	2	5736						161
3272+66	TO	3341+38	2	6872						192
TOTAL:					3553	5329	13.2	64	4708	353

PATCHING SCHEDULE										
STA	TO	STA	LENGTH	DOWEL BARS	TIE BARS	DEFORMED BARS	CLASS B PATCH	CLASS B PATCH,	SAW CUTS	STRIP REFLECTIVE
			FOOT	EACH	EACH	EXPANSION JOINT	TYPE IV, 12"	FOOT	FOOT	
3273+78	TO	3275+12	134	11	9	36	40	149	288	
3280+07	TO	3282+83	276		5			138	561	
3262+00	TO	3283+00	2100							2100
TOTAL:				11	14	36	40	287	849	2100

SIDEROAD/BUTT JOINT SCHEDULE							
SIDEROAD/STA.	L/R	WIDTH	INCIDENTAL HMA	(40800020) BIT.	(40800030)	TEMPORARY	P.C.C. BUTT
		(FOOT)	SURFACING	MAT. PRIME COAT	AGG. PRIME COAT	RAMPS	JOINTS
			(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)
3214+42.17		40	13.1	0.15	0.67	22.2	444.4
STOLLETOWN RD.	L	25	5.1	0.15	0.13	13.9	277.8
STOLLETOWN RD.	R	85	9.1	0.15	0.17	47.2	944.4
3315+14.54		40	13.1	0.15	0.67	22.2	444.4
3321+26.85		40	13.1	0.15	0.67	22.2	444.4
3341+38.42		40	13.1	0.15	0.67	22.2	444.4
TOTAL:			67	1	3	150	3000

GUARDRAIL SCHEDULE									
STA.	TO	STA.	SIDE	STEEL PLATE	TRAFFIC BARRIER	GUARDRAIL	TERMINAL	GUARDRAIL	TRAFFIC BARRIER
				BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TERMINAL, TYPE I, (SPECIAL) TANGENT		MARKERS, TYPE A		MARKERS DIRECT APPLIED
				(FOOT)	(EACH)	(EACH)	(EACH)	(FOOT)	(EACH)
3312+90	TO	3316+15	R	240		4		325	1
3313+90	TO	3316+15	L	144		4		225	1
3320+27	TO	3323+27	L	216		4		300	1
3320+27	TO	3322+77	R	168		4		250	1
3312+90			R		1		1		
3313+90			L		1		1		
3323+27			L		1		1		
3322+77			R		1		1		
TOTAL:				768	4	16	4	1100	4

FILE NAME =	USER NAME = *USER*	DESIGNED - ---	REVISED - ---
FILE#		DRAWN - ---	REVISED - ---
	PLOT SCALE = *SCALE*	CHECKED - ---	REVISED - ---
	PLOT DATE = *DATE*	DATE - -----	REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SCALE: -----		327	14, 1985-1	CLINTON	20	6
SHEET NO. OF SHEETS		STA. TO STA.		CONTRACT NO. 78E10		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT						