

MAINLINE RESURFACING

STATION TO STATION	HMA SURFACE REMOVAL, 2 1/4"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MM), N70	HMA SURFACE COURSE, MIX D, N70	STRIP REFLECTIVE CRACK CONTROL
	SQ YD	TON	TON	TON	TON	FOOT
1115+86 - 1123+21	2037.7	1.28	6.0	85.6	171.1	1470
1123+21 - 1128+04.5	1547.1	0.96	4.6	64.9	117.7	967
1128+04.5 - 1133+68.5	1653.1	1.04	5.0	69.5	138.9	1128
1133+68.5 - 1140+74.5	2031.4	1.28	6.2	85.2	170.7	1412
1140+74.5 - 1147+58	2087.6	1.30	6.4	87.8	175.4	1367
1147+58 - 1150+67.5	972.8	0.62	2.8	40.9	81.7	619
1150+67.5 - 1162+31	4912.6	3.08	14.8	206.4	412.7	2327
1162+31 - 1164+65.5	625.3	0.4	1.8	26.3	52.5	469
1164+65.5 - 1170+21.5	1992.9	1.26	6.1	83.8	167.5	1112
1170+21.5 - 1176+00	1763.6	1.12	5.2	74.1	148.2	1157
1176+00 - 1181+62	1570.5	0.98	4.7	66.0	88.6	
1181+62 - 1207+32	6853.3	4.34	20.8	291.8	583.5	
1207+32 - 1208+38	282.7	0.12	0.6	8.0	15.9	
PARKING LANES	5728.0	3.56	17.0	240.6	481.0	
TOTALS	34058.6	21.34	102.0	1430.9	2805.4	12028

FILE NAME =
#FILE#

USER NAME = #USER#

DESIGNED - ---

REVISED - ---

DRAWN - ---

REVISED - ---

PLOT SCALE = #SCALE#

CHECKED - ---

REVISED - ---

PLOT DATE = #DATE#

DATE - -----

REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

F.A.P.
RTE.

SECTION

COUNTY

TOTAL
SHEETS

SHEET
NO.

325

57RS-2

JERSEY

37

15

CONTRACT NO. 76E12

SCALE: -----

SHEET NO. 2 OF 3 SHEETS

STA. ----- TO STA. -----

FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT