

LOCATION	TEMPORARY RAMP	
	SQ YD	
	NORTH	SOUTH
STA. 1115+86	26.7	
LINCOLN ST.	66.7	
WARREN ST.	66.7	
PEARL ST.	83.3	55.6
CROSS ST.		61.1
CLAY ST.		50
ARCH ST.	55.6	55.6
PRAIRIE ST.	61.1	
LIBERTY ST.	61.1	77.8
LAFAYETTE ST.	50.0	55.6
WASHINGTON ST.	44.4	55.6
US 67	155.6	155.6
JEFFERSON ST.	44.4	44.4
GOODRICH ST.		44.4
MAPLE ST.	55.6	44.4
CARPENTER ST.	72.2	
MCBRIDE ST.		44.4
HARBERT ST.	61.7	
CURTIS ST.		50.0
MOREAN ST.	50.0	
RAILROAD	53.2	54.0
FRANKLIN ST.	88.9	
MOUND ST.	100	77.8
JUNE ST.	72.2	138.9
STA. 1208+38	26.7	
SUB-TOTAL	1296.1	1065.2
TOTAL	2361.3	

STA. TO STA.	SIZE	PAVEMENT PATCHING, TYPE IV, 13"
	FEET	SQ YD
EB Sta. 1199+25	12x20	26.7
WB Sta. 1199+25	12x20	26.7
EB Sta. 1206+70	12x20	26.7
WB Sta. 1206+70	12x20	26.7
25% FAILURES	12x20	26.7
TOTALS		133.5

SHOULDER RESURFACING					
STATION TO STATION	HMA SURFACE REMOVAL, 2 1/4"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SHOULDERS, 2 1/4"	AGGREGATE WEDGE SHOULDER, TYPE B
	SQ YD	TON	TON	TON	TON
LT. 1176+08 - 1177+92	61.3	0.02	0.1	7.7	2.7
RT. 1176+17 - 1188+15	399.3	0.12	0.6	50.3	2.9
LT. 1178+96 - 1187+70	291.3	0.09	0.4	36.7	1.2
LT. 1188+61 - 1201+40	426.3	0.13	0.6	53.7	18.7
RT. 1188+96 - 1201+21	408.3	0.13	0.6	51.4	17.9
LT. 1202+03 - 1203+70	55.7	0.02	0.1	7.0	2.4
RT. 1202+41 - 1203+50	36.3	0.01	0.1	4.6	1.6
LT. 1204+00 - 1206+65	88.3	0.03	0.1	11.1	3.9
RT. 1203+81 - 1206+08	75.7	0.02	0.1	9.5	3.3
RT. 1206+68 - 1208+38	54.0	0.02	0.1	6.8	2.4
LT. 1207+32 - 1208+38	35.3	0.01	0.1	4.5	1.5
TOTALS	1931.8	0.60	2.9	243.3	58.5

FILE NAME = #FILEL#	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = #SCALE#	DRAWN - ---	REVISED - ---			325	57RS-2	JERSEY	37	16	
	PLOT DATE = #DATE#	CHECKED - ---	REVISED - ---			CONTRACT NO. 76E12					
		DATE - ---	REVISED - ---			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					