

RESURFACING SCHEDULE						
STATION	BITUMINOUS					
	AGGREGATE (PRIME COAT)	MATERIALS (PRIME COAT)	POLY-LEVEL BINDER	HMA SURFACE CSE.	HMA SURFACE REMOVAL, 1 1/2"	HMA SURFACE SO YD
SOUTHBOUND						
575+00.00 TO 612+00.00	14.80	3.09	414.4	828.8	17111.1	
612+00.00 TO 618+00.00	3.00	0.63	84.0	168.0	3066.7	
618+00.00 TO 644+00.00	10.40	2.17	291.2	582.4	11555.6	
644+00.00 TO 649+00.00	2.50	0.53	70.0	140.0	2555.6	
649+00.00 TO 680+91.00	12.77	2.67	357.4	714.8	14182.2	
NORTHBOUND						
575+00.00 TO 608+00.00	13.20	2.76	369.6	739.2	13933.3	
608+00.00 TO 613+00.00	2.50	0.53	70.0	140.0	2555.6	
613+00.00 TO 640+00.00	10.80	2.26	302.4	604.8	11400.0	
640+00.00 TO 645+00.00	2.50	0.53	70.0	140.0	2555.6	
645+00.00 TO 680+91.00	14.37	3.00	402.2	804.4	15162.0	
SIDE ROADS						
	0.30	0.06		11.2	106	
TOTAL						
	88	18.2	2,431	4874	94,185	

SHOULDER SCHEDULE				
STATION	AGGREGATE WEDGE		HOT-MIX ASPHALT SHOULDERS, 2 1/4"	
	TON	TON	TON	TON
SOUTHBOUND				
575+00.00 TO 577+00.00	4.98		44.8	
577+00.00 TO 607+90.00	38.45		756	
607+90.00 TO 680+91.00	181.71		1655.6	
NORTHBOUND				
575+00.00 TO 577+80.00	6.97		54.9	
577+80.00 TO 602+90.00	31.24		492	
602+90.00 TO 680+91.00	194.16		1529	
TOTAL				
	458		4,532	

TEMPORARY RAMP SCHEDULE				
LOCATION	WIDTH FOOT	LENGTH FOOT	TEMPORARY RAMP	
			SO	YD
SOUTHBOUND				
STA 575+00.00	24	5	14	
STA 612+62.00	24	5	14	
STA 644+27.00	24	5	14	
STA 680+91.00	24	5	14	
NORTHBOUND				
STA 575+00.00	24	5	14	
STA 612+62.00	24	5	14	
STA 644+27.00	24	5	14	
STA 680+91.00	24	5	14	
TOTAL				
			112	

GUARDRAIL SCHEDULE							
	STEEL PLATE BEAM GUARDRAIL	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	STEEL PLATE BEAM GUARDRAIL	TRAFFIC BARRIER TERMINAL, TYPE 6	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKER, TYPE A	BARRIER WALL MARKERS, TYPE B
	FOOT	EACH	FOOT	EACH	EACH	EACH	EACH
NORTH END OF SB BARRIER	400	1	400	1	1	6	38
SOUTH END OF NB BARRIER	100	1	100	1	1	2	30
TOTAL							
	500	2	500	2	2	8	68

GLARE SCREEN BLADES	
	GLARE SCREEN BLADES 24"
	EACH
SOUTHBOUND	341
NORTHBOUND	54
20% anticipated failure	80
TOTAL	
	475

PAVEMENT MARKING SCHEDULE																	
STATION	THERMOPLASTIC PAVEMENT MARKING									TEMPORARY PAVEMENT MARKING					WORK ZONE		
	EDGE LINE					RAISED REFLECTIVE				SHORT TERM			SKIP-DASH		LETTERS & STOP BAR		PAVEMENT
	4" WHITE	4" YELLOW	4" WHITE	LETTERS & SYMBOLS	STOP BAR	PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKER	MARKING	EDGE LINE	EDGE LINE	4" WHITE	LETTERS & SYMBOLS	STOP BAR	MARKING	REMOVAL	
SOUTHBOUND																	
STA. 575+00.00 TO 612+00.00	3700.0	3700.0	92.5			46	46	1865.0	3700.00	3700.00	92.50				2704.7		
STA. 612+00.00 TO 618+00.00	600.0	600.0	15.0	52.0	12.0	8	8	305.0	600.00	600.00	15.00	52.0	12.0		438.9		
STA. 618+00.00 TO 644+00.00	2600.0	2600.0	65.0			33	33	1312.0	2600.00	2600.00	65.00				1900.8		
STA. 644+00.00 TO 649+00.00	500.0	500.0	12.5	52.0	12.0	6	6	254.0	500.00	500.00	12.50	52.0	12.0		365.7		
STA. 649+00.00 TO 680+91.00	3191.0	3191.0	79.8			40	40	1609.0	3191.00	3191.00	79.78				2332.7		
NORTHBOUND																	
STA. 575+00.00 TO 608+00.00	3300.0	3300.0	82.5			42	42	1662.0	3300.00	3300.00	82.50				2412.2		
STA. 608+00.00 TO 613+00.00	500.0	500.0	12.5	52.0	12.0	6	6	252.0	500.00	500.00	12.50	52.0	12.0		365.5		
STA. 613+00.00 TO 640+00.00	2700.0	2700.0	67.5			34	34	1360.0	2700.00	2700.00	67.50				1973.6		
STA. 640+00.00 TO 645+00.00	500.0	500.0	12.5	52.0	12.0	6	6	252.0	500.00	500.00	12.50	52.0	12.0		365.5		
STA. 645+00.00 TO 680+91.00	3591.0	3591.0	89.8			45	45	1809.0	3591.00	3591.00	89.78				2624.9		
SUB-TOTAL																	
	21182.0	21182.0	529.6	208.0	48.0	266	266	10680	21182.00	21182.00	529.55	208.0	48.0		15484.52		
TOTAL																	
	21182	21182	530	208	48	266	266	10680	21182	21182	530	208	48		15485		
GRAND TOTAL																	
		42,894		208	48	266	266	10,680		42,894		208	48		15,485		

REVIS 3-1-11

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#	#SCALE#	DRAWN	REVISED			322	(31-2, 30-2)RS-2	JEFFERSON	7	5	
PLOT DATE	#DATE#	CHECKED	REVISED			CONTRACT NO. 76E36					
		DATE	REVISED			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					
					SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA. TO STA.					