

## SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONST. TYPE CODE 0021	
		UNIT	TOTAL QUANTITIES 90% FED 10% STATE
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	2
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
X8130125	REMOVE EXISTING JUNCTION BOX	EACH	1
Z0013300	CONCRETE REMOVAL SPECIAL	SQ YD	136
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	104
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	92
* 20101400	NITROGEN FERTILIZER NUTRIENT	POUND	204
* 20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	153
* 20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	153
20200100	EARTH EXCAVATION	CU YD	2577
20300100	CHANNEL EXCAVATION	CU YD	188
20700110	POROUS GRANULAR EMBANKMENT	TON	3703
20800150	TRENCH BACKFILL	CU YD	29
* 25000115	SEEDING, CLASS 1B	ACRE	1.28
* 25000350	SEEDING, CLASS 7	ACRE	1.28
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.55
* 25100115	MULCH, METHOD 2	ACRE	2.55
* 25100630	EROSION CONTROL BLANKET	SQ YD	6175
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200
28000305	TEMPORARY DITCH CHECKS	FOOT	108
28000500	INLET AND PIPE PROTECTION	EACH	4
28100209	STONE RIP RAP, CLASS A5	TON	127
28200200	FILTER FABRIC	SQ YD	65
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	456
40600300	AGGREGATE (PRIME COAT)	TON	8
40600990	TEMPORARY RAMP	SQ YD	51
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1050
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	547
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	3
44000100	PAVEMENT REMOVAL	SQ YD	303
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	4769
44000400	GUTTER REMOVAL	FOOT	359
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2561
48101200	AGGREGATE SHOULDERS, TYPE B	TON	12
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2193
48301000	PROTECTIVE COAT	SQ YD	409

\*SPECIALTY ITEM

FILE NAME =	USER NAME = naasdp	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct\pv_wor-k\p1dot\naasdp\d0125145\d97811	5_sht_miso.dgn	DRAWN -	REVISED -			132	102 (N,L)	MASSAC	79	4	
PLOT SCALE = 40,0000' / IN.	CHECKED -	REVISED -				CONTRACT NO. 78116					
PLOT DATE = 12/20/2010	DATE -	REVISED -				ILLINOIS FED. AID PROJECT					