

SUMMARY OF QUANTITIES (CONTINUED)

CODE NO.	ITEM	CONST. TYPE CODE 0021	
		UNIT	TOTAL QUANTITIES 90% FED 10% STATE
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	18
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
* 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	127
* 81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	320
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	140
* 82103900	LUMINAIRE, SODIUM VAPOR, MULT-MOUNT, 250 WATT	EACH	4
* 82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30 AMP	EACH	1
* 83062730	LIGHT POLE, WEATHERING STEEL, 45 FT. M. H., TENON MOUNT	EACH	2
* 83062735	LIGHT POLE, WEATHERING STEEL, 45 FT. M. H., TENON MOUNT - TWIN	EACH	1
* 83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	3
* 83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	12

* SPECIALTY ITEM