

HOT-MIX ASPHALT REMOVAL LIMITS  
STA. 151+25.00

HOT-MIX ASPHALT REMOVAL LIMITS  
STA. 303+30.96

GUARDRAIL REMOVAL, STA. 309+48.02, 22.67' LT. (IL 145)  
TO STA. 152+45.23, 14.57' RT. (C.C. RD.)


PAVEMENT REMOVAL, STA. 309+86 TO 310+63

GUARDRAIL REMOVAL, STA. 309+35.63, 21.58' RT. (IL 145)  
TO STA. 10+99.63, 20.65' RT. (P.C. RD.)

HOT-MIX ASPHALT REMOVAL LIMITS  
STA. 11+85.13

LEGEND

	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"
	PAVEMENT REMOVAL
	CONCRETE REMOVAL SPECIAL



PIPE CULVERT REMOVAL STA. 151+62 LT.

STORM SEWER REMOVAL 18", STA. 152+91.05, 25.53' RT. TO 152+90.89, 25.39' LT.

PIPE CULVERT REMOVAL STA. 312+16 LT.

REMOVE EXISTING FLARED END SECTION  
STA. 316+76.72, LT. & RT.

HOT-MIX ASPHALT REMOVAL LIMITS  
STA. 317+61.60

PIPE CULVERT REMOVAL STA. 311+79 RT.

GUTTER REMOVAL, STA. 312+02.55 TO STA. 315+61.51 RT.

STORM SEWER REMOVAL 12", STA. 10+33.83, 27.77' TO 10+37.54, 19.91' RT.

JUNCTION BOX REMOVED, STA. 10+37.78, 19.42' LT.

STORM SEWER REMOVAL 18", STA. 10+37.54, 19.91' LT. TO 10+37.51, 23.13' RT.

STORM SEWER REMOVAL 12", STA. 10+38.97 TO 11+16.65' LT.

FILE NAME =  
c:\pwwork\pwwork\naasdp\d0125145\d97811

USER NAME = naasdp  
PLOT SCALE = 40,0000 / IN.  
PLOT DATE = 12/14/2010

DESIGNED -  
DRAWN -  
CHECKED -  
DATE -

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REMOVAL SHEET**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
132	102(INL)	MASSAC	79	16
				CONTRACT NO. 78116
ILLINOIS FED. AID PROJECT				