

## SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				RECONSTRUCTION, CAPACITY ADDED 0003	SAFETY (TRAFFIC SIGNALS) 0021
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4	-
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	725	725	-
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	7,257	7,257	-
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,497	1,497	-
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	12	12	-
42001300	PROTECTIVE COAT	SQ YD	1,373	1,373	-
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	465	465	-
42400800	DETECTABLE WARNINGS	SQ FT	64	64	-
44000100	PAVEMENT REMOVAL	SQ YD	3,556	3,556	-
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	49	49	-
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,798	1,798	-
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	66	66	-
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	66	66	-
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	321	321	-
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	242	242	-
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	7	7	-
50105220	PIPE CULVERT REMOVAL	FOOT	40	40	-
* 50800105	REINFORCEMENT BARS	POUND	1,828	1,828	-
54213453	END SECTIONS 18"	EACH	2	2	-
542C0223	PIPE CULVERTS, CLASS C, TYPE 1 18"	FOOT	50	50	-
* 550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	641	641	-
* 550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	137	137	-
55100500	STORM SEWER REMOVAL 12"	FOOT	105	105	-
Δ * 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1	-
* 60107700	PIPE UNDERDRAINS 6"	FOOT	20	20	-
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	4	4	-
60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	6	-

\* INDICATES SPECIAL PROVISION  
 Δ INDICATES SPECIALTY ITEM

DESIGNED BY: BAXTER & WOODMAN, INC. PROJECT: PEACE ROAD IMPROVEMENTS  
 DRAWN BY: UKB DATE: 10-27-2010  
 CHECKED BY: RWL DATE: 05-03-2010  
 DATE: 05-03-2010 FILE NAME: -081068-QNTY.dgn  
 LICENSE NO.: 184-00121 - EXPIRES 7/30/2011  
 11/07/2010 10:56:07 AM I:\Crystal Lake\UKB\081068-PeaceRoad\081068-QNTY.dgn



DESIGNED - DJS	REVISED - 08-4-2010 IDOT REVIEW
DRAWN - UKB	REVISED - 10-27-2010 IDOT REVIEW
CHECKED - RWL	REVISED -
DATE - 05-03-2010	FILE NAME - 081068-QNTY.dgn

**CITY OF DeKALB, ILLINOIS  
 PEACE ROAD  
 IMPROVEMENTS**

### SUMMARY OF QUANTITIES

SCALE: \_\_\_\_\_ STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-00-WR	DeKALB	64	5
CONTRACT NO. 87465				
FED. ROAD DIST. NO. 3   ILLINOIS FED. AID PROJECT M-5017 (043)				