SUMMARY OF QUANTITIES

	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE: RECONSTRUCTION, CAPACITY ADDED 0003	CONSTRUCTION TYPE CODE: SAFETY (TRAFFIC SIGNALS) 0021
Δ	89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	2,829	-	2,829
*Δ	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	-	1
*Δ	89502380	REMOVE EXISTING HANDHOLE	EACH	12	-	12
*Δ	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	7	-	7
*	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	5,565	5,565	-
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-
*	Z0019600	DUST CONTROL WATERING	UNIT	100	100	-
*	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,393	1,393	-
*	Z0048900	RAILROAD TRACK REMOVAL	FOOT	86	86	-
*	Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	28	28	-
*	Z0062456	TEMPORARY PAVEMENT	SQ YD	934	934	-
+	Z0076600	TRAINEES	HOUR	1,000	1,000	-
*Δ	XX002856	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM	L SUM	1	-	1
*Δ	XX004395	ELECTRIC CABLE IN CONDUIT, 600V (XLP) 2/C NO. 10	FOOT	483	-	483
*	XX005472	DRAINAGE STRUCTURE SPECIAL	EACH	12	12	-
*	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2	-
*	X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	3	3	-
*Δ	X6640565	CHAIN LINK FENCE, 7' (SPECIAL)	FOOT	250	250	-
*	X6640298	CHAIN LINK FENCE REMOVAL (SPECIAL)	FOOT	365	365	-
*	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	-
*Δ	X8140074	GROUNDING EXISTING HANDHOLE FRAME AND COVER	EACH	5	-	5
*Δ	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,146	-	1,146
*Δ	X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FOOT	299	-	299

* INDICATES SPECIAL PROVISION

Δ INDICATES SPECIALTY ITEM

\+ 0042.

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. - 184-000121 - EXPIRES 4/30/2011
23MAR2010 10:27:00 AM ...\plord-fver\DF22234.plt
u:\Cyprus\Local\pw_25\08068*Peace Rd\CADD-SURVEY\DRAWINGS\DGNS\PH2-sheets\08068-QNTY.dgn

BAXTER & WOODMAN Consulting Engineers

DESIGNED	- DJS	REVISED	-08-4-2010 IDOT REVIEW
DRAWN	- UKB	REVISED	-10-27-2010 IDOT REVIEW
CHECKED	- RWL	REVISED	-
DATE	- 05-03-2010	FILE NAME	08106B-QNTY.dgn

CITY OF DeKALB , ILLINOIS
PEACE ROAD
IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-00-WR	DeKALB	64	9

CONTRACT NO. 87465

FED. ROAD DIST. NO. 3 | ILLINOIS | FED. AID PROJECT M-5017 (043)