

CONCRETE SCHEDULE						
LOCATION	AGGREGATE BASE COURSE, TYPE B 4" (SQ YD)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (FOOT)	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH (SQ FT)	REINFORCEMENT BARS (POUND)	DETECTABLE WARNINGS (SQ FT)	PROTECTIVE COAT (SQ YD)
PEACE ROAD						
STA 126+55 TO STA 128+35	124	360	-	107	-	104
STA 128+35 TO STA 133+50	353	1,030	-	575	-	296
STA 133+50 TO STA 135+00	103	300	-	14	-	86
STA 135+00 TO STA 146+00	753	2,200	-	681	-	631
STA 146+00 TO STA 149+00	295	710	465	451	64	256
TOTAL	1,628	4,600	465	1,828	64	1,373

ROADWAY REMOVAL SCHEDULE					
LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)	PAVEMENT REMOVAL (SQ YD)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	GUARDRAIL REMOVAL (FOOT)
PEACE ROAD					
STA 126+55 TO STA 128+35	225	730	-	-	-
STA 126+76, 28' LT TO STA 130+77, 26' LT	-	-	-	-	401
STA 126+53, 28' RT TO STA 130+54, 25' RT	-	-	-	-	401
STA 128+35 TO STA 133+50	-	369	-	-	-
STA 133+50 TO STA 135+00	-	34	-	-	-
STA 135+00 TO STA 146+00	-	283	-	1,062	-
STA 146+00 TO STA 149+00	500	2,140	49	736	-
TOTAL	725	3,556	49	1,798	802

GUARD RAIL AND TRAFFIC BARRIER TERMINAL SCHEDULE						
LOCATION	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 2 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) (EACH)	GUARDRAIL MARKERS, TYPE A (EACH)	TERMINAL MARKER DIRECT APPLIED (EACH)
PEACE ROAD						
STA 126+50.6, 26' RT TO STA 126+96.6, 26' RT	-	-	1	-	-	-
STA 126+73.5, 26' LT TO STA 127+19.1, 26' LT	-	-	1	-	-	-
STA 126+96.3, 26' RT TO STA 130+83.8, 26' RT	388	-	-	-	4	-
STA 127+19.1, 26' LT TO STA 132+69.1, 26' LT	550	-	-	-	4	-
STA 130+83.8, 26' RT TO STA 130+96.3, 26' RT	-	1	-	-	-	1
STA 132+69.1, 26' LT TO STA 133+19.1, 26' LT	-	-	-	1	-	1
TOTAL	938	1	2	1	8	2

FENCING SCHEDULE				
LOCATION	CHAIN LINK FENCE, 4' (FOOT)	CHAIN LINK FENCE, 7' (SPECIAL) (FOOT)	CHAIN LINK FENCE REMOVAL (SPECIAL) (FOOT)	TEMPORARY FENCE (FOOT)
PEACE ROAD				
STA 129+00, 100' RT TO STA 132+71, 98' RT	-	-	-	400
STA 138+08, 44' LT TO STA 140+50, 34' LT	-	250	250	-
STA 143+75, 35' RT TO STA 144+75, 50' RT	115	-	115	110
TOTAL	115	250	365	510

TEMPORARY PAVEMENT MARKING SCHEDULE									
	PAVEMENT MARKING REMOVAL (SQ FT)	SHORT-TERM PAVEMENT MARKING (FOOT)	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS (SQ FT)	TEMPORARY PAVEMENT MARKING - LINE 4" (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 6" (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 8" (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 12" (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 24" (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
TOTAL FROM STAGE 2	6,661	-	-	1,150	-	-	-	-	230
TOTAL FROM STAGE 3	-	-	200	15,890	1,120	-	-	150	3,694
TOTAL FROM STAGE 4	-	-	200	15,890	1,120	-	-	150	3,694
TOTAL FROM STAGE 5	-	-	200	15,910	1,120	-	-	150	3,698
TOTAL FROM STAGE 6	-	1,347	236	21,548	290	1,058	1,131	153	5,954
TOTAL	6,661	1,347	836	70,388	3,650	1,058	1,131	603	17,270

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC. ...
 LICENSE NO. 184-00281 - EXPIRES 4/30/2011
 8/1/2010 11:49 AM
 R:\Cryofol\Loc\DL\DL\0808-PeaceRd\CADD-SURVEY\DRAWINGS\0808\PH2-8908-08\0808-SCHEDULE-QNTY.dgn



DESIGNED - DJS	REVISED - 08-4-2010 IDOT REVIEW
DRAWN - UKB	REVISED -
CHECKED - RWL	REVISED -
DATE - 05-03-2010	FILE NAME - 081068-SCHEDULE-QNTY.dgn

CITY OF DeKALB, ILLINOIS
PEACE ROAD
IMPROVEMENTS

SCALE:		STA. TO STA.	

SCHEDULE OF MATERIALS

F.A.U. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-00-WR	DeKALB	64	14
CONTRACT NO. 87465				
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT M-5017 (043)				