

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N 5TH ST	03-00289-00-BR	ADAMS	90	10
STA.		TO STA.		

CONTRACT NO. 93542

ENTRANCE IMPROVEMENT SCHEDULE

CODE NO.	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH	LENGTH	44000200	40201000	40200700	35100700	40600200	40603080	40603310	31100300	42300200	42300300		
LOCATION	FE/PE/CE/MB	FOOT	FOOT	(FROM E/PVT OR B/CURB TO END/IMPROVE)	DRIVEWAY PAVEMENT REMOVAL	AGGREGATE FOR TEMP. ACCESS (±6")	AGGREGATE SURF. CSE. TYPE A, 8"	AGGREGATE BASE COURSE TYPE A, 8"	BITUMINOUS MATERIALS (PRIME CT)	HMA BINDER CSE. IL-19.0, N50 THICKNESS	HMA BINDER CSE. IL-19.0, N50	HMA SURFACE CSE. MIX "C", N50 THICKNESS	HMA SURFACE CSE. MIX "C", N50	SUB-BASE GRANULAR MATERIAL TYPE A, 4"	PCC DRIVEWAY PAVEMENT 6"	PCC DRIVEWAY PAVEMENT 7"
	RURAL/URBAN	HMA / PCC	FOOT	FOOT	SQ YD	TON	SQ YD	SQ YD	TON	INCH	TON	INCH	TON	SQ YD	SQ YD	SQ YD
5TH STREET																
LT - 40+38.17	PE - URBAN	PCC	13.2	43.4	71.3	24								69.0	67.7	
RT - 45+20.00	CE - RURAL	AGG	12.0	31.0		19	34							13.3	12.0	
LT - 45+26.00	CE - RURAL	AGG	12.0	31.0		17	34							13.3	12.0	
RT - 45+76.00	CE - RURAL	AGG	12.0	27.4		16	29							13.3	12.0	
LT - 45+78.00	CE - RURAL	AGG	12.0	26.0		14	27							13.3	12.0	
RT - 50+17.90 (W/ HMA PARKING)	CE - URBAN	HMA	22.0 & VARIES	60.5 & VARIES	1,985	128		1,894	3,418.7	3.0	328	1.5	164	386		75
LT - 53+16.74 (PARKER HT RD)	CE - URBAN	SEAL CT	24.0	25.1 SKEW	*			151	0.2726	1.5	13	1.5	13			
RT - 54+15.50 (W/ PCC PARKING)	CE - URBAN	PCC	47.9 & VARIES	23.4 & VARIES	238									184		169
LT - 54+82.33 (W/ HMA PARKING)	PE - URBAN	HMA	11.2 & VARIES	21.6 & VARIES	98	11		85	0.1534	1.5	8	1.5	8			
10+15.5 - 11+15.0 (GARDNER PK RD)	CE - URBAN	SEAL CT	20.0	100.0	*			247	0.4436	1.5	21	1.5	21			
TOTALS					2,392.3	229	124	2,377	4,288.3		370		206	692.2	115.7	244
USE					2,393				4.3						116	

* REMOVAL OF SEAL COAT PAVEMENT IS INCIDENTAL TO EARTH EXCAVATION

LOCATION	CODE NO.	50104300*
CULVERT SIZE	CONC HDWL REMOVAL	
5TH STREET	INCH DIA	EACH
40+55.5, 19.5 LT	12	1
41+21.1, 17.9 LT	12	1
TOTAL		2

LOCATION	CODE NO.	44000300
COMB CURB GUTTER REM		
5TH STREET		FOOT
49+11.8, 16.0 R - 49+94.6, 16.0 R		83.0
49+94.6, 11.1 R - 50+06.8, 77.3 R		72.0
50+36.5, 15.6 R - 51+09.4, 16.1 R		187.0
53+17.2, 46.0 R - 53+91.1, 23.0 R		130.0
54+41.6, 23.7 R - 55+00.0, 12.8 R		65.0
TOTAL		537

LOCATION	CODE NO.	44000100
PAVEMENT REMOVAL		
5TH STREET		SQ YD
40+20.0 - 45+00.0		1,190.0
45+00.0 - 45+44.8		111.8
45+53.3 - 48+46.3		705.7
49+11.5 - 50+00.0		118.5
50+00.0 - 55+00.0		1,402.7
TOTAL		3,598.9
USE		3,599

PSBA
 POEPPING, STONE, BACH & ASSOCIATES, INC.
 ARCHITECTS ENGINEERS PLANNERS SURVEYORS
 100 S 54TH ST, P.O. BOX 708 • QUINCY, IL 62306
 WITH OFFICES IN IKEOKUK, IOWA & HANNIBAL, MISSOURI
 www.psba.com • PHONE 877-223-4605

REVISIONS	
NAME	DATE

CITY OF QUINCY, ILLINOIS
 N. 5TH STREET BRIDGE
 SCHEDULE OF QUANTITIES
 SHEET 4 OF 5

SCALE: VERT. _____
 DATE _____
 DRAWN BY: DBS
 CHECKED BY: AMW