

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N 5TH ST	03-00289-00-BR	ADAMS	90	11
STA.		TO STA.		

CONTRACT NO. 93542

LIGHTING SCHEDULE												
LOCATION	UNIT	80400100 ELECTRIC SERVICE INSTALLATION	81012600 CONDUIT IN TRENCH, 2" DIA., PVC	81100600 CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALV. STEEL	81500100 GULFBOX JUNCTION	81900200 TRENCH AND BACKFILL FOR ELECTRICAL WORK	82103900 LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	82500330 LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240 V, 60 AMP	8360820 LIGHT POLE, GALV STEEL, 40 FT. M.H., TENON MOUNT	87000110 ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 2/C NO. 8 AND NO. 10 GROUND	83600120* LIGHT POLE FOUNDATION, (SPECIAL)	87800500* CONCRETE FOUNDATION (SPECIAL)
5TH STREET	UNIT	EACH	FOOT	FOOT	EACH	FOOT	EACH	EACH	EACH	FOOT	FOOT	FOOT
L1 - L2: 49+60.0, 22.6 RT TO 49+72.0, 22.0 LT	1		63			77		1		43		4.0
L2 - L3: 49+72.0, 22.0 LT TO 50+25.0, 22.0 LT			64		1	78	1		1	59	11.0	
L2 - L4: 49+72.0, 22.0 LT TO 48+15.0, 22.0 LT			59	127	1	73	1		1	181	11.0	
L4 - L5: 48+15.0, 22.0 LT TO 46+05.0, 22.0 LT			198		1	212	1		1	193	11.0	
TOTALS USE	1		384	127	3	440	3	1	3	476	33.0	4.0

FURNISHING AND ERECTING ROW MARKERS (SPECIAL)		
LOCATION	CODE NO.	X6660115 EACH
5TH STREET		
40+54.08, 40.39 LT	PL	1
41+40.35, 40.50 LT	ROW	1
41+40.35, 25.50 RT	ROW	1
42+40.00, 110.00 LT	PE	1
43+00.00, 60.00 LT	PE	1
43+93.39, 297.31 RT	PE	1
44+00.00, 40.70 LT	PE	1
44+11.62, 305.74 RT	PE	1
44+46.27, 156.28 RT	PE	1
44+75.16, 25.24 RT	PE	1
44+95.39, 25.22 RT	ROW	1
45+03.03, 40.78 LT	ROW	1
45+96.40, 25.15 RT	ROW	1
45+94.32, 40.00 RT	PE	1
46+03.35, 40.86 LT	ROW	1
46+04.29, 60.00 LT	PE	1
46+50.00, 70.00 RT	PE	1
47+00.00, 100.00 LT	PE	1
48+00.00, 70.00 RT	PE	1
49+00.00, 80.00 LT	PE	1
49+00.00, 80.00 RT	PE	1
49+91.15, 24.84 RT	PL	1
49+91.15, 41.16 LT	PL	1
49+91.43, 50.00 RT	PE	1
51+00.00, 41.45 LT	PE	1
53+77.82, 41.14 LT	ROW	1
53+77.82, 24.88 RT	ROW	1
54+20.03, 40.41 LT	PL	1
TOTALS		28

PAVEMENT MARKING SCHEDULE																
CODE NO.	PAINT PAVEMENT MARKING															
	80400100			80400100			80400100			80400100			80400100			
	LINE 5"			LINE 5"			LINE 8"			LINE 12"			LINE 24"			LETTERS & SYMBOLS
	WHITE SOLID	YELLOW SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	
5TH STREET																
39+90 - 45+41				1102												
39+90 - 40+94					94	94	13	15								
40+20 - 41+52			132													
40+20 - 45+52	502															
42+15 - 45+42			327													
41+75 - 41+87								12								
42+24											10		10			
44+45								11								
44+70												68				
44+95								11								
45+13													10			
45+23								15								
45+56 - 53+85	829															
45+57 - 55+00				1886												
45+77 - 52+60			683													
45+76								15								
46+10								11					10			
46+25													68			
46+50								11								
49+91											10		10			
52+51													10			
52+85 - 53+09								24								
53+76											10					
KNAPHEIDE P. LOT			550													
TOTALS USE	1331	550	1142	2988	94	94	13	15	37	73	108		108			
	6,011				188		28		110		216					

10 SQ FT = BIKE SYMBOL & ARROW
68 SQ FT = STANDARD RR X-ING SYMBOL

SIGN SCHEDULE								
LOCATION	CODE NO.	72000100 SIGN PANEL - TYPE 1			72900100 METAL POST TYPE A	72900200 METAL POST TYPE B		
		SIDE	OFFSET	MESSAGE	SIZE	SQ FT	FOOT	FOOT
41+00.00	RT	22.5		W10-1 RAILROAD	3' X 3'	9		13
41+66.75	LT	41.0		R1-1 STOP	3' X 3'	9		13
42+00.00	RT	22.5		R2-1 SPEED LIMIT	24"X30"	5		14
42+00.00	RT	22.5		R7-9a NO PARK/BIKE	12"X18"	1.5	12	
43+00.00	LT	22.5		R7-9a NO PARK/BIKE	12"X18"	1.5	12	
46+50.00	RT	22.5		R7-9a NO PARK/BIKE	12"X18"	1.5	12	
50+50.00	LT	22.5		R2-1 SPEED LIMIT	24"X30"	5		14
50+50.00	LT	22.5		R7-9a NO PARK/BIKE	12"X18"	1.5	12	
52+00.00	LT	22.5		W10-1 RAILROAD	3' X 3'	9		13
52+78.25	LT	31.0		R1-1 STOP	3' X 3'	9		13
TOTALS						52	48	80

BOLLARDS	
CODE NO.	Z0004002
LOCATION	BOLLARDS
	EACH
41+86.8, 57.6 LT	1
42+15.0, 42.9 LT	1
52+75.9, 31.7 LT	1
53+39.4, 28.2 LT	1
TOTAL	4

REMOVE & REINSTALL EXISTING PARK DISTRICT BOLLARDS

PSBA
POEPPING, STONE, BACH & ASSOCIATES, INC.
ARCHITECTS ENGINEERS PLANNERS SURVEYORS
100 S 54TH ST, P.O. BOX 709 • QUINCY, IL 62306
WITH OFFICES IN IKEOKUK, IOWA & HANNIBAL, MISSOURI
www.psba.com • PHONE 877-223-4605

REVISIONS		CITY OF QUINCY, ILLINOIS	
NAME	DATE	N. 5TH STREET BRIDGE	
		SCHEDULE OF QUANTITIES SHEET 5 OF 5	
		SCALE: VERT. DRAWN BY: DBS	
		HORIZ. CHECKED BY: AMW	

PERMANENT SURVEY MARKERS, TYPE I		
LOCATION	CODE NO.	66700205 EACH
5TH STREET		
40+20.00	POT	1
41+40.35	PI	1
53+77.82	PI	1
55+44.81	PI	1
TOTALS		4