

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, COMMITMENTS, AND ADT
3-6	SUMMARY OF QUANTITIES
7	TYPICAL SECTIONS
8	SCHEDULES
9-11	PLAN SHEETS
12	DETAILS
13-25	STRUCTURE SHEETS

HIGHWAY STANDARDS

00001-08
001001-02
001006
482011-03
630001-12
630301-09
631006-08
631031-17
701006-05
701011-04
701301-04
701306-04
701311-03
701321-18
701326-04
701901-08
704001-08
780001-05
781001-04
782006-01

GENERAL NOTES

- UTILITIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA:
AT&T ILLINOIS
BOND MADISON WATER COMPANY
PLAINES MARKETING, LP
- NO SURVEY WAS PERFORMED FOR THIS PROJECT AND THE PLANS WERE CREATED USING MICROFILM AND FIELD MEASUREMENTS.
- TWO (2) CHANGEABLE MESSAGE SIGN SHALL BE REQUIRED FOR THIS PROJECT AND SHALL BE PLACED TWO (2) WEEKS PRIOR TO ANY LANE CLOSURE. THE CHANGEABLE MESSAGE SIGNS SHALL BE PLACED AT THE DIRECTION OF THE ENGINEER.

COMMITMENTS

NONE

MIX CHART

				BD Overlay
MIXTURE USE	POLY SURFACE	BINDER		POLY SURFACE
AC/PG	SBS PG 76-22	PG 64-22		SBS PG 76-22
DESIGN AIR VOIDS	4.0% @ Ndes=70	4.0% @ Ndes=70		4.0% @ Ndes=70
MIX COMPOSITION (Gradation)	IL 9.5	IL 9.5 FG		IL 9.5
FRICITION AGG	MIXTURE "D"	MIXTURE "C"		MIXTURE "D"
QUALITY MGMT PROGRAM	QC/QA	QC/QA		QC/QA
MatTranDev Required?	no	no		no

		SHOULDERS (lower)	SHOULDERS (surface)		
MIXTURE USE					
AC/PG		PG 64-22	PG 64-22		
DESIGN AIR VOIDS		4.0% @ Ndes=30	4.0% @ Ndes=30		
MIX COMPOSITION (Gradation)		IL 19.0L	IL 9.5L		
FRICITION AGG					
QUALITY MGMT PROGRAM		QC/QA	QC/QA		
MatTranDev Required?		no	no		

Plan quantities for Bituminous Concrete Surface Course items are calculated using a unit weight of 112 lb/sq yd/in (59.8 kg/sq m/25 mm thickness).

Any QCP Pay Item that has a quantity of 1600 tons or less will have two sublots each of which will be half of the Plan Quantity or half of the Adjusted Quantity by the Resident Engineer/Technician.

△ REVISED 3-2-2022

△ 2

MODEL: Default
FILE: \\hpc-pw-bechtel.com\PI\DOT\Documents\DOT_Offices\Dir\dr_8\Projects\0876F50\CADD\Draws\CADDsheets\0876F50-shh-cmmnstd.dgn

USER NAME = challandeske	DESIGNED -	REVISED - KC 3-1-22
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 3/1/2022	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, HIGHWAY STANDARDS
GENERAL NOTES, AND COMMITMENTS

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	111-BR-2	BOND	25	2
CONTRACT NO. 76P50				
ILLINOIS FED. AID PROJECT				