


# SUMMARY OF QUANTITIES

COUNTY:	JACKSON CO
ROUTE:	IL-13/U.S. 51
FUNDING:	100% STATE
LOCATION:	URBAN
	ROADWAY
	0006

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	
4200060	WELDED WIRE REINFORCEMENT	SQ YD	142	142
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	37	37
44200948	CLASS B PATCHES, TYPE I, 9 INCH	SQ YD	3	3
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	441	441
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	46	46
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQ YD	96	96
44201299	DOWEL BARS 1 1/2"	EACH	1,850	1,850
44213000	PATCHING REINFORCEMENT	SQ YD	142	142
44213200	SAW CUTS	FOOT	4,508	4,508
44213204	TIE BARS 3/4"	EACH	146	146
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	65	65
67100100	MOBILIZATION	L SUM	1	1
70102631	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	2	2
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	56	56
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1



REVISED 3-1-22  
 REV. - MS

MODEL NUMBER: MAMES  
 FILE NAME: 311215

USER NAME = SUSERS	DESIGNED -	REVISED -	
	DRAWN -	REVISED -	
PLOT SCALE = SCALES	CHECKED -	REVISED -	
PLOT DATE = SDATES	DATE -	REVISED -	

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>	
SCALE:	SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322/331	D9 PATCH 2022-3	JACKSON	7	4
			CONTRACT NO. 78891	
ILLINOIS FED. AID PROJECT				