



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 25, 2022

SUBJECT FAP Route 311 (Ogden Avenue)  
Project NHPP-V217(559)  
Section 2021-029-RS  
Cook County  
Contract No. 62N78  
Item No. 103, March 11, 2022 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added pages 91 & 92 to the Special Provisions.
4. Revised sheets 3, 4 & 8-14 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

ELECTRIC CABLE.....	55
DETECTOR LOOP REPLACEMENT AND/OR INSTALLATION (ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS) .....	55
REBUILD EXISTING HANDHOLE.....	59
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) .....	60
BLENDED FINELY DIVIDED MINERALS (BDE).....	61
COMPENSABLE DELAY COSTS (BDE).....	62
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	65
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) .....	67
FUEL COST ADJUSTMENT (BDE).....	77
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE).....	79
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) .....	80
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) .....	81
TRAINING SPECIAL PROVISIONS (BDE) .....	81
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.....	84
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) .....	86
WEEKLY DBE TRUCKING REPORTS (BDE).....	87
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) .....	87
MENTOR-PROTÉGÉ PROGRAM .....	90
CURB OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (D1).....	91

Revised 2/24/2022

## **CURB OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (D1)**

Effective: November 1, 2020

Description. This work shall consist of the complete removal and replacement of curb or combination curb and gutter. Work shall be according to Sections 440 and 606 of the Standard Specifications, State Standard 606001, District Detail BD-24 and as directed by the Engineer except as modified herein.

Curb or combination curb and gutter removal and replacement shall match the type of the existing curb or combination curb and gutter. Types may be variable and are to meet existing dimensions and field conditions. Locations of removal and replacement shall be determined by the Resident Engineer at the time of construction.

Unsuitable material to be removed, as directed by the Engineer, shall be replaced with subbase granular material, type B or additional thickness of concrete. Suitable backfill material, when required, shall be replaced as directed by the Engineer.

Epoxy coated tie bars, #6 (20) - 24" (610) long at 24" (610) centers, shall be used except when adjacent to flexible pavement. Longitudinal bars, if encountered, are not to be replaced.

Hot-mix asphalt surface removal on the existing gutter flag, if encountered, shall be included in the removal of the curb and gutter.

Saw cuts shall be according to Article 440.03 of the Standard Specifications.

½" (13) preformed expansion joints shall be used at concrete sidewalks, driveways and medians.

Method of Measurement. Concrete curb removal and replacement, or combination concrete curb and gutter removal and replacement will be measured for payment in feet (meters) along the face of concrete curb. A minimum replacement length of 4 feet is required.

Basis of Payment. This item will be paid for at the contract unit price per foot (meter) for CURB REMOVAL AND REPLACEMENT or COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT for lengths greater than 10 feet and CURB REMOVAL AND REPLACEMENT LESS THAN OR EQUAL TO 10 FEET or COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT LESS THAN OR EQUAL TO 10 FEET for lengths less than or equal to 10 feet.

Where unsuitable material is encountered in the subgrade or subbase and its removal and replacement is required by the Engineer, such removal and replacement will be paid for according to Article 109.04.

Sidewalk removal, driveway pavement removal and median surface removal will be paid for according to Article 440.08 of the Standard Specifications.

Added 2/24/2022

Portland cement concrete sidewalk will be paid for according to Article 424.13 of the Standard Specifications.

Portland cement concrete driveway pavement will be paid for according to Article 423.11 of the Standard Specifications.

Hot-mix asphalt driveway will be paid for according to Article 355.11 and 406.14 of the Standard Specifications.

Concrete median surface will be paid for according to Article 606.15 of the Standard Specifications.

Topsoil will be paid for according to Article 211.08 of the Standard Specifications.

Sodding will be paid for according to Article 252.13 of the Standard Specifications. Fertilizer for the placement of sod is not required.

Added 2/24/2022