

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	2007-024 I	DuPAGE	26	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 60C90

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT		S.N. 022-0036 FUNDS	S.N. 022-0037 FUNDS	S.N. 022-0143 FUNDS	S.N. 022-0144 FUNDS
				SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A
44000086	HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE	SQ. YD.	3,208	432	402	1,135	1,239
44201737	CLASS D PATCHES, TYPE 1, 8 INCH	SQ. YD.	2	-	2	-	-
50102400	CONCRETE REMOVAL	CU. YD.	50.1	-	-	26.4	23.7
50157300	PROTECTIVE SHIELD	SQ. YD.	1,652	592	-	600	460
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	44.6	-	-	20.9	23.7
50300260	BRIDGE DECK GROOVING	SQ. YD.	2,910	398	378	1,068	1,066
50800205	REINFORCEMENT BARS, EPOXY COATED	FOUND	9,260	-	-	4,400	4,860
50800515	BAR SPLICERS	EACH	96	-	-	48	48
52000110	PREFORMED JOINT STRIP SEAL	FOOT	331	-	-	175	156
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU. YD.	2	-	2	-	-
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL. MO.	8	2	2	2	2
67100100	MOBILIZATION	L. SUM	1	0.25	0.25	0.25	0.25
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L. SUM	1	0.25	0.25	0.25	0.25
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL. DA.	40	10	10	10	10
* 78008210	POLYUREA PAVEMENT MARKING TYPE I-LINE 4"	FOOT	2,300	320	280	900	800
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	48	8	4	20	16
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ. YD.	3,230	432	402	1,157	1,239
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ. FT.	192	48	48	48	48
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	261	180	81	-	-
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ. FT.	162	144	18	-	-
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ. FT.	1190	68	66	656	400
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	16,000	4,000	4,000	4,000	4,000
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2 "	SQ. YD.	3,208	432	402	1,135	1,239
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ. YD.	1	0.50	0.50	-	-
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ. YD.	109	33	14	30	32
Z0048665	RAILROAD PROTECTION LIABILITY INSURANCE	L. SUM	1	-	-	1	-

*
*

* SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION	
SUMMARY OF QUANTITIES IL. RTE. 59	
SCALE	DRAWN BY: D.L./F.M.
DATE: JANUARY 12, 2009	CHECKED BY: B.N.S./S.J.P.
CHRISTIAN-ROGE & ASSOC., INC. CHICAGO ILLINOIS	

REVISIONS	
NAME	DATE

Rev.