

ROADWAY LIGHTING SCHEDULE OF QUANTITIES

ITEM	UNIT	TOTAL QUANTITIES
CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	107
ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 4	FOOT	17,786
AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	4,265
REMOVE ELECTRIC CABLE FROM EMBEDDED CONDUIT	FOOT	17,732
MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6

LT-02