

100% FED.

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		U.S. 45 / 52 BRIDGE SFTY-2A	
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1	
40600300	AGGREGATE (PRIME COAT)	TON	1	1	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	23	23	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	44	44	
40600990	TEMPORARY RAMP	SQ YD	30	30	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	34	34	
42001300	PROTECTIVE COAT	SQ YD	293	293	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	352	352	
50300260	BRIDGE DECK GROOVING	SQ YD	283	283	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	416	416	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	40	40	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2	2	

* SPECIALTY ITEM

100% FED.

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		U.S. 45 / 52 BRIDGE SFTY-2A	
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1	
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1,050	1,050	
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	6	6	
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15 FT MAST ARM	EACH	6	6	
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	6	6	
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	293	293	
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48	
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3	3	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	125	125	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	1,340	1,340	
* X0325867	COMBINATION POLE MOUNTED ELECTRIC SERVICE BOX	EACH	1	1	
X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
* XX006937	GROUND ROD, 5/8" DIA. x 10 FT.	EACH	1	1	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	293	293	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	15	15	
* X0326135	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	1	1	

* SPECIALTY ITEM

FILE NAME = 60D79 500.dgn
PLOT DATE = 1/12/2009



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	S.J.P.	REVISED -	
DRAWN -	A.C.S.	REVISED -	
CHECKED -	E.J.M.	REVISED -	
DATE	JANUARY 12, 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
U.S. 45 / 52

SCALE: NONE SHEET NO. 1 OF SHEETS STA. 755+65.50 TO STA. 757+02.41

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	17 B-2-1-1	WILL	21	3
			CONTRACT NO. 60D79	