

| SUMMARY OF QUANTITIES | | | URBAN 100% FED. | CONSTRUCTION TYPE CODE | |
|-----------------------|--|-------|--------------------|---------------------------|---------------|
| CODE NO | ITEM | UNIT | | TOTAL QUANTITIES | 1000 URBAN |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 36 | 32 | 4 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 241 | 216 | 25 |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 40 | 40 | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 1,159 | 1,159 | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 1,030 | 1,030 | |
| 40603595 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 | TON | 5,890 | 5,281 | 609 |
| 42001300 | PROTECTIVE COAT | SQ YD | 585 | 585 | |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 143 | 143 | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 800 | 800 | |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 60 | 60 | |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SQ YD | 60,103 | 53,886 | 6,217 |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 143 | 143 | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 800 | 800 | |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 3,000 | 3,000 | |
| 44002220 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5" | SQ YD | 3,670 | 3,670 | |
| 44201753 | CLASS D PATCHES, TYPE II, 9 INCH | SQ YD | 300 | 300 | |
| 44201757 | CLASS D PATCHES, TYPE III, 9 INCH | SQ YD | 400 | 400 | |
| 44201759 | CLASS D PATCHES, TYPE IV, 9 INCH | SQ YD | 2,492 | 2,492 | |
| NP 55039700 | STORM SEWER TO BE CLEANED | FOOT | 2,400 | 2,400 | |
| 60262700 | INLETS TO BE RECONSTRUCTED | EACH | 3 | 3 | |
| 60300310 | FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) | EACH | 69 | 69 | |
| 60406100 | FRAMES AND LIDS, TYPE 1, CLOSED LID | EACH | 10 | 10 | |

| SUMMARY OF QUANTITIES | | | URBAN 100% FED. | CONSTRUCTION TYPE CODE | |
|-----------------------|--|--------|--------------------|---------------------------|---------------|
| CODE NO | ITEM | UNIT | | TOTAL QUANTITIES | 1000 URBAN |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 6 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | |
| 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | L SUM | 1 | 1 | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 9,390 | 9,390 | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 1,290 | 1,290 | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 41,622 | 41,622 | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 7,888 | 7,888 | |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 1,088 | 1,088 | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 996 | 996 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 3,130 | 3,130 | |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 645 | 645 | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 20,811 | 20,811 | |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 3,944 | 3,944 | |
| * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 544 | 544 | |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 498 | 498 | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 867 | 867 | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 867 | 867 | |
| * 88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 1,631 | 1,631 | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 51 | 51 | |
| X4067107 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 2,367 | 2,122 | 245 |
| NP Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 79 | 79 | |
| © Z0076600 | TRAINEES | HOURL | 500 | 500 | |

* SPECIALTY ITEM
NP - Non-participating

FILE NAME = D:\60E29-sht-500.dgn
PLOT DATE = 1/12/2009

CHRISTIAN ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

| | | | |
|------------|------------------|-----------|--|
| DESIGNED - | K.R.K. | REVISED - | |
| DRAWN - | A.C.S. | REVISED - | |
| CHECKED - | S.J.P. | REVISED - | |
| DATE - | JANUARY 12, 2009 | REVISED - | |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
WESTERN AVENUE

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

| | | | | |
|---|-------------|--------|--------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 370 | 2008-005 RS | COOK | 22 | 3 |
| | | | CONTRACT NO. 60E29 | |
| FED. ROAD DIST. NO. 111015 FED. AID PROJECT | | | | |