

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		ROADWAY 1000	PARKING LANES 1000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28	26	2				
40600300	AGGREGATE (PRIME COAT)	TON	69	67	2				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	16	1				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	3672	3672					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	250	250					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2882	2824	58				
42001300	PROTECTIVE COAT	SO YD	233	233					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	34315	33619	696				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1400	1400					
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	1521	1521					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1500	1500					
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	700	700					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	126	126					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4305	4305					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	496	496					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17399	17399					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3931	3931					

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		ROADWAY 1000	PARKING LANES 1000				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	93	93					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	541	541					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	478	478					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	496	496					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17399	17399					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3931	3931					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	180	180					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	541	541					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	26	26					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	26	26					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2616	2616					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	1351	1324	27				
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15					
© Z0076600	TRAINERS	HOURL	500	500					

© Y080
* Specialty Items
NP= Non-participating

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

10/15/2008
c:\p\collect\sl150008\slan_cdw\dm