F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	103RS-2	COOK	22	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

--- CONTRACT NO. 60F00

URBAN 100% FED

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY 1000-~~2A~~					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27	27					
40600300	AGGREGATE (PRIME COAT)	TON	134	134					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	17					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	295	295					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	105	105					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2810	2810					
42001300	PROTECTIVE COAT	SQ YD	300	300					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2150	2150					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	33395	33395					
44000600	SIDEWALK REMOVAL	SQ FT	2150	2150					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	260	260					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	602	602					
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	10	10					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	136	136					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	235	235					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	27	27					
55039700	STORM SEWERS TO BE CLEANED	FOOT	800	800					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3	3					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	52	52					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	17	17					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	6	6					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					

URBAN 100% FED

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY 1000					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7320	7320					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	330	330					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15800	15800					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2390	2390					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1120	1120					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	545	545					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1830	1830					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	330	330					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15800	15800					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2390	2390					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1120	1120					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	545	545					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	414	414					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	408	408					
88600600	DETECTOR LOOP REPLACEMENT	FOOT	2772	2772					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	70	70					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1320	1320					
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	8	8					
△ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	52	52					

△ NON-PARTICIPATING (100% STATE)

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 1/12/2009

1/12/2009
pdlrw_work$\bw$u1doc19$mpi1hw4h0108092$$design_qsdgn