

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN	I000	SFTY-2A
			TOTAL	100% FEDERAL QUANTITY	100% FEDERAL QUANTITY
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	347	347	
• 88600400	DETECTOR LOOP, SPECIAL	FOOT	2,267	2,267	
X0301424	SILICONE JOINT SEALER	FOOT	248		248
X0321316	ACCESS DOOR	EACH	2		2
X0322729	MATERIAL TRANSFER DEVICE	TON	21,592	21,592	
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	11,598		11,598
X0324914	SLOTTED DRAINS TO BE ADJUSTED	FOOT	111	111	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	207		207
• X6310195	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT), MODIFIED	EACH	1	1	
Z0006200	BRIDGE DECK SCARIFICATION	SQ YD	11,704		11,704
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	410		410
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	1,263		1,263
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	1,312		1,312
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	447	447	
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CU YD	149	149	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	10	10	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	15	15	
Z0032470	JOINT SEALER	FOOT	62		62
Z0075310	TIE BARS 3/4"	EACH	979	979	
X4420529	CLASS A PATCHES, TYPE II, 8 1/2 INCH	SQ YD	21	21	
X4420530	CLASS A PATCHES, TYPE IV, 8 1/2 INCH	SQ YD	2,907	2,907	
X0326333	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451 (SPECIAL)	L SUM	1	1	

* SPECIALTY ITEM