

PAVEMENT MARKING SCHEDULE												
STA. TO STA.	PAINT PAVEMENT MARKING			THERMOPLASTIC PAVEMENT MARKING								RAISED REFL
	4" WHT	4" YELL	6" YELL	4" WHT	4" YELL	6" YELL	8" WHT	12" WHT	12" YELL	24"WHT	LTRS & SYM	PAVT MARK
	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	SQ FT	EA
31+00 TO 41+41.05				1823	4129		663	160	415	33	46.8	30
STA. EO.												
47+89.8 TO 68+60	4142	1015	500									26
68+60 TO 95+81	5442	2722	680									35
95+81 TO 97+20	BRIDGE OMISSION											
97+20 TO 120+80	4720	2955	330									30
120+80 TO 174+12	10664	2700	1330									67
174+12 TO 226+18	10412	2572	1300									66
226+18 TO 288+43	12450	5528	1160									78
288+43 TO 341+50	10614	3055	1270									67
341+50 TO 364+00	4500	2660	350									29
364+00 TO 369+00				640		130				24		4
IL 26												
NORTH LEG				210		20				12		2
SOUTH LEG				210		20				12		2
SUBTOTALS	62944	23207	6920	2883	4129	170	663	160	415	81	46.8	436
TOTALS	86151		6920	7012		170	663	575		81	46.8	436

NOTE: THE FOLLOWING NO PASSING ZONES SHOULD BE FIELD VERIFIED BY THE ENGINEER PRIOR TO RESURFACING

EB: STA. 63+90 TO 79+75	WB STA. 47+90 TO 53+35
EB STA. 100+85 TO 116+70	WB STA. 79+75 TO 95+60
EB STA. 127+25 TO 132+55	WB STA. 106+10 TO 122+00
EB STA. 169+50 TO 180+00	WB STA. 132+50 TO 148+40
EB STA. 201+15 TO 209+10	WB STA. 180+00 TO 185+35
EB STA. 222+30 TO 254+00	WB STA. 209+10 TO 211+75
EB STA. 301+50 TO 312+00	WB STA. 238+10 TO 264+55
EB STA. 327+90 TO 349+00	WB STA. 312+00 TO 317+35
	WB STA. 338+40 TO 359+60

TEMPORARY PAVEMENT MARKING SCHEDULE										
STA. TO STA.	TEMPORARY PAVEMENT MARKING								SHORT TERM	WORK ZONE PAV'T
	4" WHT	4" YELL	6" YELL	8" WHT	12" WHT	12" YELL	24"WHT	LTRS & SYM	PAVT MARK	MARK REM.
	FT	FT	FT	FT	FT	FT	FT	SQ FT	FT	SQ FT
31+00 TO 41+41.05	1823	4129		663	160	415	33	46.8	276	31
STA. EO.										
47+89.8 TO 68+60	4142	1015	500						624	69
68+60 TO 95+81	5442	2722	680						819	91
95+81 TO 97+20	BRIDGE OMISSION									
97+20 TO 120+80	4720	2955	330						708	79
120+80 TO 174+12	10664	2700	1330						1602	178
174+12 TO 226+18	10412	2572	1300						1563	173
226+18 TO 288+43	12450	5528	1160						1869	207
288+43 TO 341+50	10614	3055	1270						1593	177
341+50 TO 364+00	4500	2660	350						675	75
364+00 TO 369+00	640		130				24		96	11
IL 26										
NORTH LEG	210		20				12		33	4
SOUTH LEG	210		20				12		33	4
SUBTOTALS	65827	27336	7090	663	160	415	81	46.8	9891	1098
TOTALS	93163		7090	663	575		81	46.8	9891	1098

NOTE: THE FOLLOWING NO PASSING ZONES SHOULD BE FIELD VERIFIED BY THE ENGINEER PRIOR TO RESURFACING

EB: STA. 63+90 TO 79+75	WB STA. 47+90 TO 53+35
EB STA. 100+85 TO 116+70	WB STA. 79+75 TO 95+60
EB STA. 127+25 TO 132+55	WB STA. 106+10 TO 122+00
EB STA. 169+50 TO 180+00	WB STA. 132+50 TO 148+40
EB STA. 201+15 TO 209+10	WB STA. 180+00 TO 185+35
EB STA. 222+30 TO 254+00	WB STA. 209+10 TO 211+75
EB STA. 301+50 TO 312+00	WB STA. 238+10 TO 264+55
EB STA. 327+90 TO 349+00	WB STA. 312+00 TO 317+35
	WB STA. 338+40 TO 359+60