

MAINLINE SCHEDULE											
LOCATION MILE MARKERS		CENTERLINE REPAIR HMA SURF REM SPECIAL SQ YD	HOT-MIX ASPH. SURF. REM 2" SQ YD	HOT-MIX ASPH. SURF. REM 4" SQ YD	HOT-MIX ASPH. SURF. REM 5" SQ YD	POLY. HOT-MIX ASPH. SURF. MIX E N105 TON	POLY. HOT-MIX ASPH. BINDER IL-19.0 N105 TON	POLY. BIT MATL PR CT GAL	AGG PR CT TON	MIX FOR CR, JTS, & FLANGEWAYS TON	LEVEL BINDER (HM) TON
LASALLE COUNTY											
EASTBOUND DRIVING LANE											
75.8 TO 76.1	1584			2112		177	296	380.2	4.2	0.63	1.06
77.4 TO 77.7	1584			2112		177	296	380.2	4.2	0.63	1.06
78.9 TO 79.2	1584			2112		177	296	380.2	4.2	0.63	1.06
80.2 TO 80.3	528			704		59	99	126.7	1.4	0.21	0.35
89.3 TO 89.7	2112		2816			315		225.3	5.6	0.84	1.41
89.9 TO 90.2	1584	352				79		28.2	0.7	0.11	0.18
93.8 TO 93.9	528				704	59	138	126.7	1.4	0.21	0.35
95.1 TO 95.6	2640				3520	296	690	633.6	7.0	1.06	1.76
EASTBOUND PASSING LANE											
75.8 TO 76.1	1584			2112		177	296	380.2	4.2	0.63	1.06
96 TO 96.2	1056				1408	118	276	253.4	2.8	0.42	0.70
WESTBOUND DRIVING LANE											
75.6 TO 76	2112			2816		237	394	506.9	5.6	0.84	1.41
77 TO 77.1	528			704		59	99	126.7	1.4	0.21	0.35
77.2 TO 77.3	528			704		59	99	126.7	1.4	0.21	0.35
78.4 TO 78.5	528			704		59	99	126.7	1.4	0.21	0.35
78.5 TO 78.7	1056	235				53		18.8	0.5	0.07	0.12
80.1 TO 80.2	528			704		59	99	126.7	1.4	0.21	0.35
81.3 TO 81.5	1056			1408		118	197	253.4	2.8	0.42	0.70
88.7 TO 90	1584	352				79		28.2	0.7	0.11	0.18
93.8 TO 93.9	528				704	59	138	126.7	1.4	0.21	0.35
95.7 TO 95.8	300				400	34	78	72.0	0.8	0.12	0.20
100.9 TO 101	528				704	59	138	126.7	1.4	0.21	0.35
WESTBOUND PASSING LANE											
75.6 TO 76	2112			2816		237	394	506.9	5.6	0.84	1.41
77.2 TO 77.3	528			704		59	99	126.7	1.4	0.21	0.35
GRUNDY COUNTY											
WESTBOUND DRIVING LANE											
103.7 TO 103.8	100				133	11	26				
TOTAL	26800	939	2816	19712	7573	2818	4244	5187.8	61.8	9.27	15.45

LOOPS IN PAVEMENT IN AREA AROUND MM99.8-OMIT-DO NOT DISTURB-SEE DETAIL

SHOULDER REPAIR*		
LOCATION MILE MARKERS	HMA SURF. REM 5" SQ YD	HMA SHLD 5" TON
LASALLE COUNTY VARIOUS LOCATIONS	600	600
TOTAL	600	600

* THIS ITEM IS A CONTINGENCY ITEM TO REPAIR HMA SHOULDER DUE TO TRAFFIC DAMAGE TO SHOULDER DURING PAVING OF MAINLINE

PAVEMENT MARKING SCHEDULE							
LOCATION STATION TO STATION	LENGTH	THERMO PVMT MARK LINE 4" FOOT	THERMO PVMT MARK LINE 6" FOOT	RAISED REFLEC PVT MK EACH	RAISED REFLEC PVT MK REMO EACH	SHORT-TERM PVT. MARK. FOOT	WORK-ZONE PVT. MARK. REM. SQ FT
LASALLE COUNTY							
EASTBOUND DRIVING LANE							
75.8 TO 76.1	1584	1584	396	40	40	158	52
77.4 TO 77.7	1584	1584	396	40	40	158	52
78.9 TO 79.2	1584	1584	396	40	40	158	52
80.2 TO 80.3	528	528	132	13	13	53	17
89.3 TO 89.7	2112	2112	528	53	53	211	70
89.9 TO 90.2	1584	1584	396	40	40	158	52
93.8 TO 93.9	528	528	132	13	13	53	17
95.1 TO 95.6	2640	2640	660	66	66	264	87
EASTBOUND PASSING LANE							
75.8 TO 76.1	1584	1584					
96 TO 96.2	1056	1056	264		26	106	35
WESTBOUND DRIVING LANE							
75.6 TO 76	2112	2112	528	53	53	211	70
77 TO 77.1	528	528	132	13	13	53	17
77.2 TO 77.3	528	528	132	13	13	53	17
78.4 TO 78.5	528	528	132	13	13	53	17
78.5 TO 78.7	1056	1056	264	26	26	106	35
80.1 TO 80.2	528	528	132	13	13	53	17
81.3 TO 81.5	1056	1056	264	26	26	106	35
88.7 TO 90	1584	1584	396	40	40	158	52
93.8 TO 93.9	528	528	132	13	13	53	17
95.7 TO 95.8	300	300	75	8	8	30	10
100.9 TO 101	528	528	132	13	13	53	17
WESTBOUND PASSING LANE							
75.6 TO 76	2112	2112					
77.2 TO 77.3	528	528					
GRUNDY COUNTY							
WESTBOUND DRIVING LANE							
103.7 TO 103.8	100	100	25	3	3	10	3
TOTAL	26800	26800	5644	564	564	2258	745