

| SUMMARY OF QUANTITIES |   |        | 100% FED.      |
|-----------------------|---|--------|----------------|
| CODE NO.              | CONSTRUCTION CODE TYPE:<br>ITEM                           | UNIT   | I000           |
|                       |   |        | TOTAL QUANTITY |
| 40600115              | POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)             | GALLON | 25011          |
| 40600300              | AGGREGATE (PRIME COAT)                                    | TON    | 465            |
| 40600400              | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS                | TON    | 70             |
| 40600755              | POLYMERIZED LEVELING BINDER (HAND METHOD), N105           | TON    | 117            |
| 40600895              | CONSTRUCTING TEST STRIP                                   | EACH   | 1              |
| 40603550              | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105 | TON    | 28820          |
| 44000157              | HOT-MIX ASPHALT SURFACE REMOVAL, 2"                       | SQ YD  | 232,869        |
| 44000196              | HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL                  | SQ YD  | 17250          |
| 42001200              | PAVEMENT FABRIC   | SQ YD  | 1125           |
| 44213200              | SAW CUTS  | FOOT   | 5840           |
| 44201055              | CLASS B PATCHES, TYPE II, 17 INCH                         | SQ YD  | 596            |
| 44201057              | CLASS B PATCHES, TYPE III, 17 INCH                        | SQ YD  | 282            |
| 44201053              | CLASS B PATCHES, TYPE IV, 17 INCH                         | SQ YD  | 864            |
| 48203017              | HOT-MIX ASPHALT SHOULDERS, 5"                             | SQ YD  | 600            |
| 67000400              | ENGINEER'S FIELD OFFICE, TYPE A                           | CAL MO | 2              |
| 67100100              | MOBILIZATION  | L SUM  | 1              |
| 70300100              | SHORT-TERM PAVEMENT MARKING                               | FOOT   | 7951           |
| 70301000              | WORK ZONE PAVEMENT MARKING REMOVAL                        | SQ FT  | 2624           |
| 78100100              | RAISED REFLECTIVE PAVEMENT MARKER                         | EACH   | 1988           |
| 78300200              | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL                 | EACH   | 1988           |
| X0325969              | PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE BOARD       | CAL DA | 45             |
| X7010805              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL) | L SUM  | 1              |
| X7800610              | URETHANE PAVEMENT MARKING - LINE 4"                       | FOOT   | 159020         |
| X7800630              | URETHANE PAVEMENT MARKING - LINE 6"                       | FOOT   | 19878          |
| Z0017100              | DOWEL BARS  | EACH   | 1800           |
| Z0075300              | TIE BARS  | EACH   | 316            |

• SPECIALTY ITEMS