

SUMMARY OF QUANTITIES				URBAN		RURAL	
				INTERSTATE ROADWAY		INTERSTATE ROADWAY	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000 100% FED		1000 100% FED	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10583	222		10361	
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	100			100	
21400100	GRADING AND SHAPING DITCHES	FOOT	9525	200		9325	
* 25000210	SEEDING, CLASS 2A	ACRE	2.3	0.05		2.25	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	200	4		196	
* 25000600	PHOSPHORUS FERTILIZER NUTRIENT	POUND	200	4		196	
* 25000800	POTASSIUM FERTILIZER NUTRIENT	POUND	200	4		196	
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	10695	222		10473	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	222	5		217	
28000300	TEMPORARY DITCH CHECKS	EACH	98	40		58	
28000400	PERIMETER EROSION BARRIER	FOOT	200			200	
28100825	STONE DUMPED RIPRAP, CLASS B3	TON	4295	415		3880	
28100830	STONE DUMPED RIPRAP, CLASS B4	TON	61	61			
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	126	24		102	
40600300	AGGREGATE (PRIME COAT)	TON	846	157		689	
40600895	CONSTRUCTING TEST STRIP	EACH	2			2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3040	1520		1520	
40600990	TEMPORARY RAMP	SQ YD	374	187		187	

*SPECIALTY ITEM