



NOTES:

1. DELINEATORS, SPECIAL shall be constructed of 4" x 4" x 6' treated timber.
2. Each post shall be buried a minimum of 36 inches deep.
3. Timber shall be treated in accordance with Article 1007.12 of the Standard Specifications. Waterborne Preservatives, ASA and CCA, shall have A 0.40 lbs/ft³ minimum retention.
4. Amber Reflectors shall meet the requirements of Article 1097.03 of the Standard Specifications.
5. Amber Reflectors shall be included in the cost of DELINEATORS, SPECIAL

FILE NAME = 1-74 Morton General File.dgn	USER NAME = k3menkk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MEDIAN CROSSOVER CLOSURE DETAIL (STA. 716 + 74.50)			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000' / IN.	DRAWN -	REVISED -		NOT TO SCALE	SHEET NO. 1 OF 1 SHEETS	STA. 716+74.50	74	(90-15)RS-3	TAZEWELL	60	44
	PLOT DATE = 2/11/2009	CHECKED -	REVISED -		CONTRACT NO. 68508							
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							