

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
741	*	PIATT	48	4

\* BRS-4&(9,10)RS-3

**SUMMARY OF QUANTITIES**

LOCATION OF WORK:

FAP 741 (IL 105)  
 PIATT COUNTY  
 STATION 383+70.00  
 TO  
 STATION 56+95.70  
 RURAL TWO-LANE  
 100% FEDERAL  
 I000

CONSTRUCTION TYPE CODE:

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19,441.0
40600300	AGGREGATE (PRIME COAT)	TON	197.0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	7,849.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,007.0
40600990	TEMPORARY RAMP	SQ YD	294.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	16,409.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	676.0
40800030	AGGREGATE (PRIME COAT)	TON	7.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	503.0
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	185,911.0
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	7,489.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	1,311.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	337.0
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	48.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,277.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	1.0
60255500	MANHOLES TO BE ADJUSTED	EACH	1.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0