

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
741	*	PIATT	48	5

\* BRS-4&(9,10)RS-3

### SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAP 741 (IL 105)  
 PIATT COUNTY  
 STATION 383+70.00  
 TO  
 STATION 56+95.70  
 RURAL TWO-LANE  
 100% FEDERAL  
 1000

CONSTRUCTION TYPE CODE:

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20,763.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	163,003.0
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	342.0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	823.0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	261.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,307.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS & SYMBOLS	SQ FT	141.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17,865.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	342.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	823.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	261.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	145,138.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	997.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	997.0
X0325283	BITUMINOUS SHOULDER REMOVAL AND REPLACEMENT 8"	SQ YD	1,000.0
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	9.0

\* SPECIALTY ITEM