

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
741	*	PIATT	48	21

* 8RS-4&(9,10)RS-3

TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	40600982	40600990	44000152	44000154	40600100	40600300	40600625	40603310	LOCATION
				HMA SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL 0.75 IN	HMA SURFACE REMOVAL 1.25 IN	BITUMINOUS MATERIALS PRIME COAT	AGGREGATE MATERIALS PRIME COAT	LEVELING BINDER (MM) MIX C N 50 0.75 IN	HMA SURF CSE MIX C, N 50 IL 9.5, 1.5 IN	
				SQ YD	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	
STA. 383 + 70 TO 384 + 00	25.00	30.00	83.33	83.33	13.89			8.33	0.08	1.75	7.04	BEGINNING OF SECTION
STA. 384 + 00 TO 422 + 17	25.00	3,817.30	10,603.61			10,603.61		1,060.36	10.60	446.47	895.16	
STA. 420 + 82 TO 422 + 46	25.00	163.70	454.72			454.72		45.47	0.45	19.15	38.39	
STA. 422 + 46 TO 422 + 76	25.00	30.00	83.33	83.33	13.89			8.33	0.08	1.75	7.04	S.N. 074-0030 (NORTH SIDE)
STA. 423 + 44 TO 423 + 74	25.00	30.00	83.33	83.33	13.89			8.33	0.08	1.75	7.04	S.N. 074-0030 (SOUTH SIDE)
STA. 423 + 74 TO 452 + 58	25.00	2,883.80	8,010.56			8,010.56		801.06	8.01	337.28	676.25	
STA. 452 + 58 TO 458 + 74	31.00	616.20	2,122.47			2,122.47		212.25	2.12	89.32	179.01	
STA. 458 + 74 TO 459 + 00	37.00	26.00	106.89			106.89		10.69	0.11	4.50	9.01	
STA. 510 + 00 TO 510 + 89	37.00	89.00	365.89			365.89		36.59	0.37	15.39	30.84	
STA. 510 + 89 TO 514 + 98	34.00	409.00	1,545.11				1,545.11	154.51	1.55		130.27	BEMENT-HAMMOND ROAD
STA. 514 + 98 TO 515 + 88	37.00	89.60	368.36			368.36		36.84	0.37	15.50	31.05	(FAP 812)
STA. 515 + 88 TO 520 + 96	31.00	508.10	1,750.12			1,750.12		175.01	1.75	73.65	147.60	
STA. 520 + 96 TO 521 + 26	25.00	30.00	83.33	83.33	13.89			8.33	0.08	1.75	7.04	FAP 812
STA. 600 + 00 TO 600 + 55	38.00	54.60	230.53		21.11		230.53	23.05	0.23		19.43	T.R. 167 (700N)
STA. 460 + 72 TO 462 + 72	38.00	200.30	845.71				845.71	84.57	0.85		71.27	IL 105 (WEST LEG)
STA. 462 + 72 TO 468 + 80	33.00	607.80	2,228.60			2,228.60		222.86	2.23	93.78	187.91	
STA. 468 + 80 TO 549 + 73	25.00	8,092.30	22,478.61			22,478.61		2,247.86	22.48	946.46	1,897.64	
STA. 549 + 73 TO 550 + 03	25.00	30.00	83.33	83.33	13.89			8.33	0.08	1.75	7.04	S.N. 074-0080 (EAST)
STA. 550 + 84 TO 551 + 14	25.00	30.00	83.33	83.33	13.89			8.33	0.08	1.75	7.04	S.N. 074-0080 (WEST)
STA. 551 + 14 TO 579 + 13	25.00	2,799.05	7,775.14			7,775.14		777.51	7.78	327.37	656.38	
STA. 579 + 13 TO 579 + 43	25.00	30.00	83.33	83.33	13.89			8.33	0.08	1.75	7.04	S.N. 074-8061 (EAST)
STA. 580 + 05 TO 580 + 35	25.00	30.00	83.33	83.33	13.89			8.33	0.08	1.75	7.04	S.N. 074-8030 (WEST)
STA. 580 + 35 TO 645 + 64	25.00	6,528.79	18,135.53			18,135.53		1,813.55	18.14	763.60	1,531.00	
STA. 645 + 64 TO 645 + 94	25.00	30.00	83.33	83.33	13.89			8.33	0.08	1.75	7.04	S.N. 074-0079 (EAST)
STA. 646 + 86 TO 647 + 16	25.00	30.00	83.33	83.33	13.89			8.33	0.08	1.75	7.04	S.N. 074-0079 (WEST)
STA. 647 + 16 TO 738 + 10	25.00	9,094.25	25,261.81			25,261.81		2,526.18	25.26	1,063.65	2,132.60	
STA. 738 + 00 TO 885 + 17	25.00	14,716.82	40,880.06			40,880.06		4,088.01	40.88	1,721.25	3,451.09	
STA. 885 + 17 TO 888 + 47	33.00	329.68	1,208.83			1,208.83		120.88	1.21	50.87	101.93	
STA. 888 + 47 TO 889 + 22	41.00	75.50	343.94			343.94		34.39	0.34	14.47	28.98	
STA. 889 + 22 TO 892 + 40		318.00	1,438.62				1,438.62	143.86	1.44		121.22	CERRO GORDO INTERSECTION
STA. 892 + 40 TO 898 + 03	22.00	563.00	1,376.22				1,376.22	137.62	1.38		116.26	
STA. 898 + 03 TO 1032 + 44	25.00	13,441.30	37,336.94			37,336.94		3,733.69	37.34	1,572.07	3,151.98	
STA. 263 + 11 TO 263 + 41	26.00	30.00	86.67	86.67	14.44			8.67	0.09	1.82	7.32	END OF SECTION (IL 32)
STA. 263 + 41 TO 268 + 34	26.00	493.00	1,424.22			1,424.22		142.42	1.42	59.96	120.21	
STA. 268 + 34 TO 269 + 39	38.00	104.90	442.91			442.91		44.29	0.44	18.63	37.33	
STA. 269 + 39 TO 271 + 18	38.00	178.90	755.36				755.36	75.54	0.76		63.66	IL 105/32 INTERSECTION
STA. 271 + 18 TO 277 + 13	32.00	594.79	2,114.81			2,114.81		211.48	2.11	89.00	178.34	
STA. 48 + 87 TO 49 + 81		94.00	622.22		24.06			622.22	0.62		52.38	C.H. 12
STA. 50 + 18 TO 50 + 87		68.70	675.73					675.73	0.68		56.84	IL 105 (WEST)
STA. 50 + 87 TO 52 + 35	48.00	148.30	790.93			790.93		79.09	0.79	33.26	66.61	
STA. 52 + 35 TO 54 + 17	42.00	182.00	849.33			849.33		84.93	0.85	35.73	71.56	
STA. 54 + 17 TO 56 + 66	31.00	248.70	856.63			856.63		85.66	0.86	36.05	72.25	
STA. 56 + 66 TO 56 + 96	26.00	30.00	86.67	86.67	14.44			8.67	0.09	1.83	7.32	END OF SECTION (IL 105 W)
STA. 268 + 34 TO 272 + 34	38.00	400.00	1,688.89						1.69			
STA. 50 + 18 TO 51 + 18		100.00	807.88						0.81			
GRAND-TOTAL				1,007.0	213.0	185,911.0	7,489.0	19,441.0	197.0	7,849.0	16,409.0	

PLOT DATE = 1/22/2009
 FILE NAME = c:\pvc\work\PI\DOT\CEARL\CKJD\0101437\0129\text.dgn
 PLOT SCALE = 42.3529 / IN
 USER NAME = ceerlckjd