

SCHEDULE OF QUANTITIES

TABULATION OF PARTIAL DEPTH PATCHING

WESTBOUND PATCHING				EXISTING OVERLAY DEPTH (IN)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)	EASTBOUND PATCHING				EXISTING OVERLAY DEPTH (IN)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)
STATION	LANE	LENGTH (FT)	WIDTH (FT)				STATION	LANE	LENGTH (FT)	WIDTH (FT)			
					-	-							
					-	-							
					-	-							
1174+50	WB	4.0	11.0	3.50	4.9	1.8	1174+50	EB	4.0	11.0	3.50	4.9	1.8
					-	-	1168+43	EB	4.0	11.0	3.50	4.9	1.8
1163+62	WB	4.0	11.0	3.50	4.9	1.8	1163+62	EB	4.0	11.0	3.50	4.9	1.8
					-	-	1161+49	EB	4.0	11.0	3.50	4.9	1.8
1159+46	WB	6.0	6.0	4.25	4.0	1.6					-	-	
1158+06	WB	6.0	6.0	4.25	4.0	1.6					-	-	
1157+50	WB	4.0	11.0	4.25	4.9	2.0	1157+50	EB	4.0	11.0	4.25	4.9	2.0
1148+50	WB	4.0	11.0	4.25	4.9	2.0	1148+50	EB	4.0	11.0	4.25	4.9	2.0
1146+00	WB	4.0	11.0	4.25	4.9	2.0	1146+00	EB	4.0	11.0	4.25	4.9	2.0
1145+10	WB	6.0	6.0	4.25	4.0	1.6					-	-	
1144+33	WB	4.0	11.0	4.25	4.9	2.0	1144+33	EB	4.0	11.0	4.25	4.9	2.0
1143+43	WB	4.0	11.0	4.25	4.9	2.0	1143+43	EB	4.0	11.0	4.25	4.9	2.0
1142+31	WB	4.0	11.0	4.25	4.9	2.0	1142+31	EB	4.0	11.0	4.25	4.9	2.0
1138+00	WB	4.0	11.0	4.25	4.9	2.0	1138+00	EB	4.0	11.0	4.25	4.9	2.0
1136+77	WB	4.0	11.0	4.25	4.9	2.0	1136+77	EB	4.0	11.0	4.25	4.9	2.0
WESTBOUND SHEET TOTALS							EASTBOUND SHEET TOTALS						
					60.9	24.3						72.4	28.0