

SCHEDULE OF QUANTITIES

TABULATION OF PARTIAL DEPTH PATCHING

WESTBOUND PATCHING				EXISTING OVERLAY DEPTH (IN)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)	EASTBOUND PATCHING				EXISTING OVERLAY DEPTH (IN)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)
STATION	LANE	LENGTH (FT)	WIDTH (FT)				STATION	LANE	LENGTH (FT)	WIDTH (FT)			
1486+09	WB	4.0	12.0	3.50	5.3	1.9	1486+09	EB	4.0	12.0	3.50	5.3	1.9
1484+00	WB	4.0	12.0	3.50	5.3	1.9	1484+00	EB	4.0	12.0	3.50	5.3	1.9
1483+09	WB	4.0	12.0	3.50	5.3	1.9	1483+09	EB	4.0	12.0	3.50	5.3	1.9
1479+27	WB	4.0	12.0	3.50	5.3	1.9						-	-
1478+00	WB	4.0	12.0	3.50	5.3	1.9						-	-
1473+10	WB	4.0	12.0	3.50	5.3	1.9	1473+10	EB	4.0	12.0	3.50	5.3	1.9
					-	-	1472+93	EB	4.0	12.0	3.50	5.3	1.9
1467+54	WB	4.0	12.0	3.50	5.3	1.9						-	-
1466+48	WB	6.0	12.0	3.50	8.0	2.9						-	-
1465+50	WB	4.0	12.0	3.50	5.3	1.9	1465+50	EB	4.0	12.0	3.50	5.3	1.9
1464+08	WB	4.0	12.0	3.50	5.3	1.9	1464+08	EB	4.0	12.0	3.50	5.3	1.9
1463+10	WB	4.0	12.0	3.50	5.3	1.9	1463+10	EB	4.0	12.0	3.50	5.3	1.9
1462+08	WB	4.0	12.0	3.50	5.3	1.9	1462+08	EB	4.0	12.0	3.50	5.3	1.9
1441+02	WB	6.0	6.0	3.50	4.0	1.5						-	-
					-	-	1439+15	EB	6.0	12.0	3.50	8.0	2.9
1438+53	WB	4.0	12.0	3.50	5.3	1.9	1438+53	EB	4.0	12.0	3.50	5.3	1.9
1438+08	WB	4.0	12.0	3.50	5.3	1.9						-	-
1432+09	WB	4.0	12.0	3.50	5.3	1.9	1432+09	EB	4.0	12.0	3.50	5.3	1.9
WESTBOUND SHEET TOTALS					86.7	31.5	EASTBOUND SHEET TOTALS					66.7	24.3

FILE NAME =	USER NAME = stultsjw	DESIGNED -	REVISED -
ct:\pw\work\PWIDOT\STULTSJW\0117834\0570506-shit-schedule.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(28)RS-4 & (29,30)RS-2	MCLEAN	54	20
CONTRACT NO. 70506				
ILLINOIS FED. AID PROJECT				