

SCHEDULE OF QUANTITIES

MAINLINE HOT MIX ASPHALT SURFACE REMOVAL SCHEDULE							
LOCATION	LENGTH	WIDTH	AREA	HOT MIX ASPHALT SURFACE REMOVAL 2 1/4" 44000158	HOT MIX ASPHALT SURFACE REMOVAL VARIABLE DEPTH 44000198	HOT MIX ASPHALT SURFACE REMOVAL 3/4" 44000152	HOT MIX ASPHALT SURFACE REMOVAL BUTT JOINT 40600982
	FEET	FEET	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
MCLEAN COUNTY							
STATION 1133+00 TO 1134+00	100.00	25.00	277.78	6,775.11	88.90		
STATION 1134+00 TO 1159+98	2,598.00	22.00	6,350.67		4,618.70		
STATION 1159+98 TO 1169+06	908.00	28.00	2,824.89		40.00	13,184.89	
STATION 1169+06 TO 1202+96	3,390.00	28.00	10,546.67				
STATION 1202+96 TO 1493+64	29,061.00	30.00	96,870.00			96,768.60	100.00
BRIDGE OMISSION 1493+56.58 TO 1494+43.42 (SN 057-0070)	86.84						
STATION 1494+15 TO 1518+50	2,407.00	30.00	8,023.33			7,853.04	246.70
TOTAL	38,464		124,893	6,775	4,748	117,807	347

MAINLINE RESURFACING SCHEDULE										
LOCATION	LENGTH	WIDTH	AREA	BITUMINOUS PRIME COAT 40800010	AGGREGATE PRIME COAT 40800030	HOT MIX ASPHALT LEVEL BINDER 3/4" 40600635	HOT MIX ASPHALT SURFACE COURSE MIX C, N70 1-1/2" 40603315	TEMPORARY RAMP * 40600990	HOT MIX ASPHALT SHOULDERS 48203100	AGGREGATE SHOULDERS TYPE B ** 48101200
	FEET	FEET	SQ YD	GALLONS	TONS	TONS	TONS	SQ YD	TONS	TONS
MCLEAN COUNTY										
STATION 1133+00 TO 1134+00	100.00	33.00	366.67	1,468.91	35.97	276.99		201.50	504	3.50
STATION 1134+00 TO 1159+98	2,598.00	38.00	10,969.33							554
STATION 1159+98 TO 1169+06	908.00	28.00	2,824.89	2,005.73	53.49	561.61	1,123.21	34.00		269.87
STATION 1169+06 TO 1202+96	3,390.00	28.00	10,546.67							
STATION 1202+96 TO 1493+64	29,061.00	30.00	96,870.00	14,530.29	387.47	4,064.28	8,136.96	173.00		1,827.69
BRIDGE OMISSION 1493+56.58 TO 1494+43.42 (SN 057-0070)	86.84									
STATION 1494+15 TO 1518+50	2,407.00	30.00	8,023.33	1,214.96	32.40	328.52	680.38	24.00		148.00
TOTAL	38,464		129,801	19,220	509	5,231	10,495	433	504	2,249

* These quantities include TEMPORARY RAMPS for the sideroads after the HMA SURFACE REMOVAL, BUTT JOINT.

** These quantities include AGGREGATE SHOULDERS, TYPE B for the sideroads.