

100% FED

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	*	ADAMS	108	3
STA.		TO STA.		
FED. ROAD DIST. NO. 6		ILLINOIS	FED. AID PROJECT	
• (1-5)RS-1; (1-6)RS				
CONTRACT NO. 72694				

SUMMARY OF QUANTITIES							
CODE NO.	ITEM	UNIT	TOTAL	RURAL ROADWAY 1000-2A	URBAN ROADWAY 1000-2A	SN 001-0050 SN 001-0051 X120-2A	SN 001-0045 SN 001-0048 SN 001-0049 X220-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	159	159			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	81	81			
20200100	EARTH EXCAVATION	CU YD	219	219			
20200200	ROCK EXCAVATION	CU YD	25	25			
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	14	14			
20201400	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	449	449			
21400100	GRADING AND SHAPING DITCHES	FOOT	13,945	13945			
25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	635	635			
28000500	INLET AND PIPE PROTECTION	EACH	9	9			
28001000	AGGREGATE (EROSION CONTROL)	TON	434	434			
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	7,052	7052			
XX005519	STONE DUMPED RIPRAP, CLASS A4 (SPECIAL)	TON	2,009	2009			
28200200	FILTER FABRIC	SQ YD	12,088	12088			
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	211	211			
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	387	387			
35300700	PORTLAND CEMENT CONCRETE BASE COURSE 12"	SQ YD	34	34			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	362.5	309.2	53.3		
40600300	AGGREGATE (PRIME COAT)	TON	1,908	1700	208		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	774	774			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	6,182	6115	67		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	4,289	4181	108		
40600990	TEMPORARY RAMP	SQ YD	726	668	58		
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	34,616	29324	5292		

URBAN ROADWAY STATION 236+00.00 TO STATION 288+81.55

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____