F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	*	ADAMS	908	5
STA.		TO STA.		
FED. ROAD DIST. NO. 6	ILLINOIS	FED. AID PROJECT		

* (1-5)RS-1; (1-6)RS

CONTRACT NO. 72694

100% FED

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	RURAL ROADWAY 1000-2A	URBAN ROADWAY 1000-2A	SN 001-0050 SN 001-0051 X120-2A	SN 001-0045 SN 001-0048 SN 001-0049 X220-2A
50157305	PROTECTIVE SHIELD	L SUM	1				1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	70			70	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	12,520			12520	
50800515	BAR SPLICERS	EACH	56			56	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	301			301	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION 12"	EACH	1	1			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTION 24"	EACH	1	1			
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTION 30"	EACH	1	1			
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTION 36"	EACH	1	1			
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTION 42"	EACH	1	1			
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	846				846
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	255	255			
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1			
60262700	INLETS TO BE RECONSTRUCTED	EACH	6	6			
60265505	MEDIAN INLET (604101) TO BE RECONSTRUCTED	EACH	11	11			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	15	15			
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	44	44			
60610900	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	76	76			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	868	868			
60622400	CONCRETE MEDIAN, TYPE SM-6.06	SQ FT	1,407	1407			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	5,775	5225	550		
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	450	450			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	10	8	2		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	16	16			

* SPECIALTY ITEM

URBAN ROADWAY STATION 236+00.00 TO STATION 288+81.55

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY