

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	*	ADAMS	108	15

STA. TO STA.
 FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT

(1-5)RS-1; (1-6)RS
CONTRACT NO. 72694

PATCHING SCHEDULE											
*	STATION	NOTES	LENGTH	WIDTH	AREA	PATCHING CL A, TY2, 8"	PATCHING CL A, TY3, 8"	PATCHING CL A, TY4, 8"	SAW CUTS	PATCH REINFORCEMENT	TIE BARS
			FT	FT	SQYD	SQYD	SQYD	SQYD	FT	SQYD	EACH
<i>SOUTHBOUND I-172</i>											
1	237+05	DL	6	12	8.0	8.0			60.0	8.0	
2	237+05	PL	6	12	8.0	8.0			60.0	8.0	
3	235+95	DL	6	12	8.0	8.0			60.0	8.0	
4	235+95	PL	6	12	8.0	8.0			60.0	8.0	
5	233+90	DL	35	12	46.7			46.7	118.0	46.7	17
6	226+45	PL	12	12	16.0		16.0		72.0	16.0	
7	210+89	PL	5	12	6.7	6.7			58.0	6.7	
8	202+46	PL	5	12	6.7	6.7			58.0	6.7	
9	186+77	DL	5	12	6.7	6.7			58.0	6.7	
10	179+67	PL	8	12	10.7	10.7			64.0	10.7	
11	178+29	PL	5	12	6.7	6.7			58.0	6.7	
12	177+89	PL	5	12	6.7	6.7			58.0	6.7	
13	177+60	PL	5	12	6.7	6.7			58.0	6.7	
14	172+90	PL	5	12	6.7	6.7			58.0	6.7	
15	172+00	PL	5	12	6.7	6.7			58.0	6.7	
16	170+36	PL	5	12	6.7	6.7			58.0	6.7	
17	166+35	PL	5	12	6.7	6.7			58.0	6.7	
18	155+25	PL	5	12	6.7	6.7			58.0	6.7	
19	140+85	DL	5	12	6.7	6.7			58.0	6.7	
20	139+80	PL	5	12	6.7	6.7			58.0	6.7	
21	139+53	PL	5	12	6.7	6.7			58.0	6.7	
22	135+00	PL	5	12	6.7	6.7			58.0	6.7	
23	135+00	DL	5	12	6.7	6.7			58.0	6.7	
24	128+32	PL	9	12	12.0	12.0			66.0	12.0	
25	128+12	DL	5	12	6.7	6.7			58.0	6.7	
26	127+76	PL	6	12	8.0	8.0			60.0	8.0	
27	115+35	DL	8.7	12	11.6	11.6			65.4	11.6	
28	110+20	PL	5	12	6.7	6.7			58.0	6.7	
29	109+53	DL	5	12	6.7	6.7			58.0	6.7	
30	109+36	PL	5	12	6.7	6.7			58.0	6.7	
31	94+31	DL	5	12	6.7	6.7			58.0	6.7	
32	79+32	PL	5	12	6.7	6.7			58.0	6.7	
33	76+00	PL	6	12	8.0	8.0			60.0	8.0	
34	75+10	DL	5	12	6.7	6.7			58.0	6.7	
35	75+10	PL	5	12	6.7	6.7			58.0	6.7	
36	74+89	DL	5	12	6.7	6.7			58.0	6.7	
37	274+10	DL	24	12	32.0			32.0	96.0	32.0	11
38	267+05	PL	14	12	18.7		18.7		76.0	18.7	
39	266+20	PL	9	12	12.0	12.0			66.0	12.0	
40	266+00	DL	17.8	12	23.7		23.7		83.6	23.7	
41	264+20	DL	43	12	57.3			57.3	134.0	57.3	21
42	263+50	DL	16	12	21.3		21.3		80.0	21.3	
43	262+04	DL	5	12	6.7	6.7			58.0	6.7	
44	261+50	DL	5	12	6.7	6.7			58.0	6.7	
45	261+50	PL	5	12	6.7	6.7			58.0	6.7	
46	249+57	DL	10	12	13.3	13.3			68.0	13.3	
47	246+30	PL	7.4	12	9.9	9.9			62.8	9.9	
48	243+35	DL	14	12	18.7		18.7		76.0	18.7	
49	242+12	DL	5	12	6.7	6.7			58.0	6.7	
50	241+38	DL	14	12	18.7		18.7		76.0	18.7	
51	240+70	DL	8.5	12	11.3	11.3			65.0	11.3	
52	240+10	DL	6	12	8.0	8.0			60.0	8.0	
53	239+78	DL	8	12	10.7	10.7			64.0	10.7	
54	239+44	DL	6	12	8.0	8.0			60.0	8.0	
55	238+80	DL	5	12	6.7	6.7			58.0	6.7	
56	205+17	DL	5	12	6.7	6.7			58.0	6.7	
57	198+43	DL	7	12	9.3	9.3			62.0	9.3	
58	179+17	DL	5	12	6.7	6.7			58.0	6.7	
59	163+86	DL	5	12	6.7	6.7			58.0	6.7	
60	94+57	DL	6.5	12	8.7	8.7			61.0	8.7	
61	91+82	DL	5	12	6.7	6.7			58.0	6.7	
62	71+74	DL	5	12	6.7	6.7			58.0	6.7	
63	65+90	DL	26	12	34.7			34.7	100.0	34.7	12
64	65+90	PL	14	12	18.7		18.7		76.0	18.7	
TOTALS					714.5	408.0	135.8	170.7	4141.8	714.5	61

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY JJS
 HORIZ. CHECKED BY LLQ
 DATE 08/04/2004