

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
172	*	ADAMS	108	28

STA. TO STA.
 FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT
 • (1-5)RS-1; (1-6)RS
CONTRACT NO. 72694

PREFORMED PLASTIC PAVEMENT MARKING , TYPE B (INLAID) LETTERS & SYMBOLS	
LOCATION	ARROWS (SQ FT)
COLUMBUS ROAD (TR 349)	
RAMP A	
LEFT-TURN LANE	15.6
THROUGH LANE	23.0
RAMP C	
LEFT-TURN LANE	15.6
THROUGH LANE	23.0
LEFT-TURN LANE WEST OF SN.001-0048	46.8
LEFT-TURN LANE EAST OF SN.001-0048	46.8
IL 104	
RAMP A	
THROUGH LANE	23.0
RAMP C	
THROUGH LANE	23.0
US 24	
RAMP A	
THROUGH LANE	11.5
LEFT-TURN LANE	31.2
RIGHT-TURN LANE	31.2
TOTAL =	290.7

URETHANE PAVEMENT MARKING - LINE 5"		
LOCATION	DOUBLE YELLOW (FOOT)	WHITE EDGE LINE (FOOT)
COLUMBUS ROAD (TR 349)		
35+48.85 TO 43+52.19 (MEDIAN)	1606.6	
44+37 TO 55+58.12 (MEDIAN)	2242.3	
56+40 TO 64+75 (MEDIAN)	1670.0	
LT 35+48.85 TO 36+54		105.2
LT 37+39 TO 42+00		461.0
LT 43+68.78 TO 56+21.34		1252.6
LT 57+69.65 TO 64+75.00		705.4
RT 35+48.85 TO 42+26.22		677.4
RT 43+74.52 TO 56+28.93		1254.4
RT 58+03.72 TO 61+62.31		352.6
RT 62+90.95 TO 64+75		184.1
TOTAL =	5518.9	4992.7

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID) - 8"	
LOCATION	SOLID WHITE (FOOT)
COLUMBUS ROAD (TR 349)	
ISLAND @ RAMP A	163
ISLAND @ RAMP C	180
TOTAL =	343

URETHANE PAVEMENT MARKING - LINE 5"	
LOCATION	WHITE EDGE LINE (FOOT)
IL 104	
RAMP A	
RT 0+00 TO 19+72	1972
LT 06+64 TO 19+72	1308
RAMP B	
RT 01+25 TO 26+74	2549
LT 01+25 TO 15+16	1391
RAMP C	
RT 0+00 TO 18+50	1850
LT 0+60 TO 18+50	1210
RAMP D	
RT 0+11 TO 25+61	2550
LT 0+11 TO 13+40	1329
US 24	
RAMP A	
RT 0+ 00 TO 20+70	2070
LT 06+41 TO 20+50	1409
RAMP D	
RT 0+13 TO 25+80	2567
0+24 TO 13+78	1354
TOTAL =	21559

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID) - LINE 24"	
LOCATION	SOLID WHITE STOP BARS (FOOT)
COLUMBUS ROAD (TR 349)	
RAMP A	
56+51.40	18
57+02.90	18
RAMP C	
42+76.26	18
43+46.50	18
HORSESHOE VALLEY DRIVE	
63+44.75	12
US 24	
RAMP A	
20+27.00	18
20+45.00	18
TOTAL =	120

URETHANE PAVEMENT MARKING, LINE 6"	
LOCATION	SOLID WHITE (FOOT)
COLUMBUS ROAD (TR 349)	
LEFT-TURN LANES	
53+75.78 TO 55+60.79	185.0
44+37.10 TO 46+15.85	178.8
TOTAL =	363.8

URETHANE PAVEMENT MARKING, LINE 5"	
LOCATION	WHITE EDGE LINE (FOOT)
COLUMBUS ROAD (TR 349)	
RAMP A	
RT 00+00 TO 24+42	2442
LT 06+45 TO 24+11	1766
RAMP B	
RT 00+40 TO 21+00	2060
LT 00+40 TO 09+00	860
RAMP C	
RT 00+00 TO 23+64	2364
LT 06+52 TO 23+20	1668
RAMP D	
RT 00+23 TO 21+14	2091
LT 00+23 TO 09+10	887
TOTAL =	14138

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID) - LINE 12"		
LOCATION	SOLID WHITE DIAGONALS & CHEVRONS (FOOT)	SOLID YELLOW DIAGONALS & CHEVRONS (FOOT)
COLUMBUS ROAD (TR 349)		
ISLAND @ RAMP A	47	
ISLAND @ RAMP C	63	
MEDIAN WEST OF SN 001-0048		85
MEDIAN EAST OF SN 001-0048		104
TOTAL =	110	189

LOCATION	PREFORMED PLASTIC PAVEMENT MARKING TYPE B, LINE 5" SKIP-DASH (FOOT)	URETHANE PAVEMENT MARKING - LINE 5" EDGE LINE (FOOT)
I-172		
SB MAINLINE		
75+24 TO 288+81.55	5339.4	42715.1
0+00 TO 247+56	6189.0	49512.0
NB MAINLINE		
78+25 TO 288+81.55	5264.1	42113.1
0+00 TO 247+31.66	6182.9	49463.3
TOTAL =	22975.4	183803.5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 SCALE: VERT. HORIZ. DATE: 08/04/2004
 DRAWN BY JJS
 CHECKED BY LLQ