

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				100% FEDERAL
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	16
40600300	AGGREGATE (PRIME COAT)	TON	75	75
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,216	1,216
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,859	1,859
40600990	TEMPORARY RAMP	SQ YD	100	100
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	6,369	6,369
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	136	136
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	4,361	4,361
44000198	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	31,034	31,034
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	290	290
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	40	40
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	140	140
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,280	1,280
48203006	HOT-MIX ASPHALT SHOULDERS, 2 1/4"	SQ YD	1,024	1,024
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	325	325
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	11	11
* 63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	508	508
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	7	7
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,038	4,038
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	74,150	74,150
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	737	737
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	74,150	74,150
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	308	308
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	26	26
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	11	11
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	300	300
*	<i>SPECIALTY ITEMS</i>			

SUMMARY OF QUANTITIES				100% FEDERAL
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A

FILE NAME = USER NAME = coxjw  
 c:\pw\work\pwidot\coxjw\dms23631\shstsoq.dgn  
 PLOT SCALE = 106.0000" / IN.  
 PLOT DATE = Feb-05-2009 04:18:13PM

DESIGNED - JWC  
 DRAWN - JWC  
 CHECKED - RSC  
 DATE -  
 REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE. 566	SECTION (1-NRHM,2)RS-3	COUNTY Scott	TOTAL SHEETS 30	SHEET NO. 3
CONTRACT NO. 72882				
FED. ROAD DIST. NO. (ILLINOIS) FED. AID PROJECT				