

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**PROPOSED PAVEMENT SCHEDULE**

LOCATION				SUB-BASE GRANULAR MATERIAL, TYPE B, 100MM	PORTLAND CEMENT CONCRETE BASE COURSE, 200MM	BITUMINOUS MATERIALS (PRIME COAT)		AGGREGATE (PRIME COAT)	LEVEING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	AGGREGATE SHOULDERS, TYPE B, 150MM	HOT-MIX ASPHALT SHOULDERS, 150MM
						PRIOR TO BINDER/BASE COURSE	PRIOR TO SURFACE COURSE					
STATION	TO	STATION	LT/RT	M3111100	M3530200	M4060100		M4060300	M4062135	M4063340	M4812150	M4820550
				SQ M	SQ M	LITER	LITER	M TON	M TON	M TON	SQ M	SQ M
<b>RURAL</b>												
0+915.000	TO	0+935.000	LT&RT			56.44	56.44	0.48	1429.32	14.71	30.00	36.00
0+935.000	TO	2+756.900	LT&RT			5420.15	5420.15	46.46	1429.32	1412.34	5318.26	3227.49
				0.00	0.00	5476.60	5476.60	46.94		1427.04	5348.26	3263.49
<b>OBLONG</b>												
2+756.900	TO	3+394.700	LT	1068.32	382.68	892.92	892.92	7.65		232.67		
2+756.900	TO	2+770.950	RT			20.90	20.90	0.18		5.45	20.54	12.64
2+770.950	TO	3+394.700	RT	1044.78	374.25	873.25	873.25	7.49		227.54		
3+394.700	TO	3+736.200	LT	572.01	204.90	705.20	705.20	6.04	1395.65	183.75		
3+394.700	TO	3+736.200	RT	1220.86	853.75	705.20	705.20	6.04		183.75		
3+736.200	TO	4+475.071	LT	1237.61	443.32	1034.42	1034.42	8.87		269.54		
3+736.200	TO	4+379.000	RT	1076.69	385.68	899.92	899.92	7.71		234.49		
4+379.000	TO	4+475.071	RT	218.56	115.29	134.50	134.50	1.15		35.05		
				6438.83	2759.87	5266.30	5266.30	45.14	1395.65	1372.25	20.54	12.64
<b>RURAL</b>												
4+475.071	TO	4+633.500	LT&RT			471.33	471.33	4.04	74.38	122.81	377.86	285.17
4+633.500	TO	4+653.500	LT&RT			28.51	63.00	0.39	1.47	16.42		
4+653.500	TO	4+874.474	LT&RT				607.28	2.60		181.38		
				0.00	0.00	499.83	1141.61	7.03	75.8421	320.61	377.86	285.17
<b>TOTAL</b>				6438.83	2759.87	11242.73	11884.51	99.12	2900.81	3119.90	5746.66	3561.31
<b>TOTALS ROUNDED FOR SUMMARY SHEET</b>				6,439	2,760	22,486		100	2,901	3,120	5,747	3,562

**DETECTABLE WARNINGS**

LOCATION		DETECTABLE WARNINGS	LOCATION		DETECTABLE WARNINGS
		M4248000			M4248000
STATION	LT/RT	SQ M	STATION	LT/RT	SQ M
<b>OBLONG</b>					
2+886.0	LT	0.63	3+109.4	RT	1.20
2+898.2	LT	0.63	3+116.8	RT	0.76
2+971.2	LT	0.63	3+128.7	RT	0.63
2+983.4	LT	0.63	3+205.2	RT	0.63
3+109.4	LT	1.20	3+217.4	RT	0.63
3+117.1	LT	0.74	3+292.4	RT	0.76
3+128.7	LT	0.63	3+304.3	RT	0.63
3+205.6	LT	0.74	3+410.6	RT	0.63
3+217.4	LT	0.63	3+420.6	RT	0.63
3+292.1	LT	0.63	3+426.7	RT	0.63
3+304.0	LT	0.76	3+440.1	RT	0.63
3+379.3	LT	0.71	3+447.5	RT	0.63
3+391.2	LT	0.83	3+456.9	RT	0.63
3+566.8	LT	0.71	3+466.4	RT	0.63
3+578.7	LT	0.72	3+478.4	RT	0.63
3+652.7	LT	0.77	3+488.7	RT	0.63
3+665.3	LT	0.75	3+498.7	RT	0.63
3+739.1	LT	0.63	3+526.4	RT	0.63
3+751.7	LT	0.72	3+532.9	RT	0.63
3+826.1	LT	0.63	3+565.8	RT	0.71
3+838.3	LT	0.71	3+578.5	RT	0.71
3+912.9	LT	0.63	3+653.4	RT	0.72
3+925.1	LT	0.63	3+664.5	RT	0.63
			3+675.1	RT	0.63
			3+688.6	RT	0.63
			3+692.1	RT	0.63
			3+700.5	RT	0.63
			3+704.0	RT	0.63
			3+712.4	RT	0.63
			3+739.8	RT	0.63
			3+751.8	RT	0.71
			3913.2	RT	0.71
			3924.9	RT	0.71
			4150.2	RT	0.63
			4161.4	RT	0.63
<b>SUB-TOTALS</b>		16.29			23.37
<b>TOTAL</b>					39.66
<b>TOTALS ROUNDED FOR SUMMARY SHEET</b>					39.7

PLT DATE = 2/6/2009  
FILE NAME = H:\4420\Contract 74349\SHI\_014\_sch.a11\_schedules\_v8.dgn

REVISIONS	
NAME	DATE
L.W.J.	08/28/08

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
SCALE NO SCALE DRAWN BY KOJ  
DATE AUGUST 28, 2008 3 CHECKED BY LWJ

H. M. & G. NO. 4420